



PONDICHERY UNIVERSITY
ELECTRICAL WING

V. MOUROUGAVELOU
ASSISTANT ENGINEER (E)

Ref: PU/ELW/AC/13-14/ 1364

R.V.NAGAR, KALAPET,
PUDUCHERRY - 14.

Date: 13/12/2013

Sub: Supply of Split type air conditioner -Quotation called for- Reg.
-oOo-

Sealed quotation is invited for following split type air conditioners subject to the terms and condition stipulated below.

The quotation should reach this office in the prescribed format enclosed herewith on or before 26/12/2013 upto 3.00 pm and the same will be opened on the same day at 3.30pm at Puducherry Campus.

Terms & Conditions:

1. Copper pipe should be used between indoor and outdoor unit of the AC unit.
2. The condenser and evaporator coil of the AC unit should be of copper coil.
3. The rate should be firm and not subject to any variation thereof.
4. The rate quoted shall be inclusive freight, excise duty, sales tax, transportation etc.,.
5. A warranty for 5 years for compressor and 1 year for machine shall be given for the AC Units invariably at the time of installation.
6. Payment will be paid only after satisfactory supply, installation and commissioning of the AC machines in the University premises.
7. The sealed cover should be superscripted with "Quotation for split AC"
8. The quotation rate should carry at least 6 month validity period.

(V.MOUROUGAVELOU)
ASSISTANT ENGINEER (E)

To

**PONDICHERRY UNIVERSITY
ELECTRICAL WING**

S.No	Description	Qty	Unit	Rate	Amount
1.	<i>Supplying, Installing, Testing and Commissioning of 1.0 ton Hi-wall split air conditioner with 4KVA V-Guard make stabilizer including making connection, drilling the wall /altering window making good the same etc., as required. Make: Onida/Voltas/LG/blue star/Panasonic/ETA</i>	1 no.	Each		
2.	<i>Extra insulated copper pipe for 1 ton split air conditioner including wire.</i>	1 mtr	metre		
3.	<i>Supplying, Installing, Testing and Commissioning of 1.5 ton Hi-wall split air conditioner with 4KVA V-Guard make stabilizer including making connection, drilling the wall /altering window making good the same etc., as required. Make: Onida/Voltas/LG/Blue star/Panasonic/ETA</i>	1 no.	Each		
4.	<i>Extra insulated copper pipe for 1.5 ton split air conditioner including wire.</i>	1 mtr	metre		
5.	<i>Supplying, Installing, Testing and Commissioning of 2 ton Hi-wall split air conditioner with 5 KVA V-Guard make stabilizer including making connection, drilling the wall /altering window making good the same etc., as required. Make: Onida/Voltas/LG/Blue star/Panasonic/ETA</i>	1 no.	Each		
6.	<i>Extra insulated copper pipe for 2 ton split air conditioner including wire.</i>	1 mtr	metre		
7.	<i>Supply of heavy duty readymade angle of Mild steel suitable for mounting 1/1.5/2 ton split air conditioner outdoor unit including anchor fasteners.</i>	1 no.	Each		

CONTRACTOR/SUPPLIER


ASSISTANT ENGINEER (E)