

PONDICHERRY UNIVERSITY
ENGINEERING WING

Er.N.SANKARAMOURTHY, B.E.,
EXECUTIVE ENGINEER

No.PU/EW/NIQ/2017-18/

Date: 09.06.2017

NOTICE INVITING QUOTATIONS

For and on behalf of Pondicherry University, Executive Engineer, Engineering wing, Pondicherry University invites sealed quotations from the eligible contractors for the work of “Providing galvalume roofing sheet shed for Diesel generator at Dept. of Earth Science building”. The rates should be filled in the schedule enclosed with this and placed in a sealed cover by superscribing the name of the work in the cover as mentioned above. An amount of Rs.2,350/- has to be furnished towards EMD which shall be in the form of demand draft from any one of the nationalized banks payable at Pondicherry, drawn in favour of the Finance officer, Pondicherry University. The notice with schedule can also be downloaded from the University website. www.pondiuni.edu.in

The filled in quotation shall to be placed in the tender box kept in the reception counter at Dr.B.R.Ambedhkar Administrative Block, Pondicherry University. The quotations will be received up to 3.00 p.m. on 21.06.2017 and will be opened at 3.30 p.m. on the same day in the presence of tenderers those who present at the time of opening.

The Executive Engineer, Engineering wing, Pondicherry University reserves the right to accept or reject any or all quotation without assigning any reason thereof.

EXECUTIVE ENGINEER

Encl: Schedule

PONDICHERY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of the work: Providing galvalume roofing sheet shed for Diesel Generator at Dept. of Earth Science building

S.No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1 2.8.1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 Sqm on plan) including dressing of sides and ramming of bottoms , lift upto 1.5m, including getting out the excavated soil and disposal of surplus excavated soil as directed , within a lead of 50m -All kinds of soil	3		Cum	
2 4.1.10	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering.- All work upto plinth level -1:5:10 (1 cement:5coarse sand : 10 graded stone aggregate 40mm nominal size)	2		Cum	
3 4.1.3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering.- All work upto plinth level -1:2:4 (1 cement:2coarse sand : 4 graded stone aggregate 20mm nominal size)	6		Cum	
4 6.1.2	Brick work with FPS bricks of class designation 35 in foundation and plinth in cement mortar 1:6 (1 cement : 6 coarse sand)	2		Cum	
5 10.16. 1	Steel work in built up tubular trusses including cutting, hoisting fixing in position and applying a priming coat of approved steel primer welded and bolted including special shaped washers etc.	395		Kg	

	complete. Hot finished welded type tubes				
6 10.19	Providing and fixing M.S. round holding down with nuts and washer plates completes.	25		Kg	
7 MR	Additional labour charges for making the required curved shape pipe in roof truss work (65mm dia)	10		Mt.	
8 13.61. 1	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade - Two or more coats on new work	9		Sqm	
9 12.70	Providing and fixing colour coated galvalume sheet of 550 M.P.A yield of AZ 150 strength formed as per patterned steel rib profile with the depth of 31mm pitch of 250mm and overall width of 1060mm and thickness 0.5mm with required J or C hook bolts and nuts 8mm dia G.S paint and working etc., complete excluding the cost of purlin , rafter and truss etc.,	28		Sqm	
10 13.1.2	12mm cement plaster of mix :Cement mortar 1:6 (1 cement : 6 fine sand)	4		Sqm	
11 13.47. 1	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade - New work (Two or more coats applied @ 1.43 ltr / 10 Sqm over and including base coat of water proofing cement paint applied @ 2.20 kg/10 Sqm).	4		Sqm	
12 MR	Additional labour charges for making the required curved shape for Galvalume roofing sheet etc.,	28		Sqm	
	Total				

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 30 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) Vat @ 3.5% will be deducted from the bill.

Contractor

Executive Engineer