

PONDICHERRY UNIVERSITY
ENGINEERING WING

Er.N.SANKARAMOURTHY, B.E.,
EXECUTIVE ENGINEER

No.PU/EW/NIQ/2017-18/

Date: 13.02.2018

NOTICE INVITING QUOTATIONS

For and on behalf of Pondicherry University the Executive Engineer, Pondicherry University invites sealed quotations from the eligible / working contractors for the work of “Replacing the roofing sheet at head room of library and special repairs to the library”. The rates should be filled in the schedule enclosed with this and placed in a sealed cover by superscribing the name of the work in the cover as mentioned above. An amount of Rs.1,700/- has to be furnished towards EMD which shall be in the form of demand draft from any of the nationalized banks payable at Pondicherry, drawn in favour of the Finance officer, Pondicherry University. The NIQ may also be downloaded from the University web site www.pondiuni.edu.in

The filled in quotations shall be placed in the tender box kept in the reception counter at Dr.B.R.Ambedhkar Administrative Block, Pondicherry University. The quotations will be received up to 3.00 p.m. on 22.02.2018 and will be opened at 3.30 p.m. on the same day in the presence of tenderers those who present at the time of opening.

The Executive Engineer, Pondicherry University reserves the right to accept or reject any or all quotations without assigning any reason thereof.

EXECUTIVE ENGINEER

Encl: Schedule

PONDICHERY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of the work: Replacing the roofing sheet at head room of library and special repairs to the library

S. No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1 15.28.1	Dismantling roofing including ridges, hips valleys and gutters etc. and stacking the material within 50m lead of - G.S.Sheet.	50.00		sqm	
2 12.70	Providing and fixing colour coated galvalume sheet of 550 M.P.A yield of AZ 150 strength formed as per patterned steel rib profile with the depth of 31mm pitch of 250mm and overall width of 1060mm and thickness 0.5mm with required J or C hook bolts and nuts 8mm dia G.S paint and working etc., complete excluding the cost of purlin , rafter and truss etc.,	50.00		sqm	
3 32.50 .1A	Raising of intercepting chamber by dismantling the old R.C.C. slab, removing the I.C. cover and frame from the chamber and raising the chamber height with brick work in cement mortar 1:4 (one cement and four sand), refixing the frame in position by laying reinforced cement concrete 1:1.5:3 (One cement one and half sand and three HBG metal) including curing but excluding the cost of reinforcement, finishing the top, inside and outside plastering with 20mm thick in cement mortar 1:3(one cement three sand), the rate includes all materials, providing barricading,caution board, watch and ward etc.,complete till the completion of work with minimum	2.00		no	

	hindrance to the traffic.- 30cm height.				
4 4.2.3	Providing and laying cement concrete in retaining walls , return walls (any thickness) including attached pilasters,columns, piers,abutments, pillars, posts,struts, buttresses, string or lacing courses, parapets, coping bed blocks , anchor blocks, plain window sills, fillets etc upto floor five level, excluding the cost of centring,shuttering and finishing:1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size)	1.00		cum	
5 MR	Providing and fixing at all height false ceiling including including fixing the gypsum board with ceiling section and perimeter channels ceiling fixed to wall at 450mm centre to centre with 25mm long drive-all screws @ 230mm interval including jointing and fixing to a flush finish of tapered and square edges of the board with recommended filler, jointing tapes, finisher and two coats of primer suitable for board as per manufactures specification and also including the cost of making openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitable fixed all complete as per drawing and specification but excluding the cost of painting with : 12.5mm thick tapered edge gypsum board conforming to IS: 2095 – part I, including Providing and fixing double scaffolding system (cup lock type)and dismantling after completion of work	13.00		Sqm	
6 2.27C. 1	Supplying and filling with gravel (excluding rock) in layers not exceeding 20cm in depth, breaking clods, watering, rolling each layer with 1/2 tonne roller,or	17.00		cum	

	wooden or steel rammers ,and rolling every 3rd and top-most layer with power roller minimum 8 tonnes capacity including all leads and lift (payment will be made based on level measurement				
7 16.68	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M-30 grade made by block making machine with strong vibratory compaction and of approved size and design /shape laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with coarse sand etc.filling the joints with courses and etc.all complete	28.00		sqm	
	Total				

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 10 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.

EXECUTIVE ENGINEER