

PONDICHERRY UNIVERSITY
ENGINEERING WING

Er.N.SANKARAMOURTHY, B.E.,
ASSISTANT ENGINEER

No.PU/SE/Grill Gate/2012-13

Date: 27.07.2012

NOTICE INVITING QUOTATIONS (THIRD CALL)

For and on behalf of Pondicherry University, the Assistant Engineer, Pondicherry University invites sealed quotations from the eligible/working contractors/Specialized firms for the work of "Providing and fixing grill gate at road in between ladies hostel and stadium near culvert in the Pondicherry University".

The notice with schedule can also be downloaded from the University web site www.pondiuni.edu.in and submitted. Quotations should be accompanied by crossed Demand Draft drawn in favour of Finance Officer, Pondicherry University for Rs.2,850/- towards Earnest money deposit.

The sealed quotations may either be sent by Registered/Speed post to the Assistant Engineer of the University or may be dropped in the tender box kept in the reception counter at Dr.B.R.Ambedhkar Administrative Block, Pondicherry University. The quotations will be received up to 3.00 p.m. on 08.08.2012 and will be opened at 3.30 p.m. on the same day in the presence of tenderers who are present at the time of opening.

The Superintending Engineer, Pondicherry University reserves the right to accept or reject any or all quotations without assigning any reason thereof.

ASSISTANT ENGINEER

Encl: Schedule

PONDICHERY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of work: Providing and fixing grill gate at road in between ladies hostel and stadium near culvert in the Pondicherry University

S. No.	Description	Qty.	Unit	Rate Rs.P	Amount Rs.P.
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms , lift upto 1.5m, including getting out the excavated soil and disposal of surplus excavated soil as directed , within a lead of 50m -All kinds of soil	1.75	Cum		
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering.- All work upto plinth level -1:5:10 (1 cement:5coarse sand : 10 graded stone aggregate 40mm nominal size)	0.25	Cum		
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering.- All work upto plinth level -1:2:4 (1 cement:2coarse sand : 4 graded stone aggregate 20mm nominal size)	1.50	Cum		
4	Steel work welded in built up section/ framed work including cutting hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In grating, frames, guard bar, ladder, railings, brackets, gates and similar works.	1450	Kg		
5	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade - Two or more coats on new work.	50	Sqm		
6	Providing and fixing 1mm Galvanised steel Plain Sheet for Steel Grill Work Including cost of welding charges and including one coat of priming coat etc. complete.	175	Kg		
	Total				

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within a period of 30 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The materials to be used in the work shall be got approved by the Engineer-in – Charge before commencement of work.
- v) The rate quoted shall including all taxes and levies.
- vi) Necessary I.T and VAT will be deducted from the bill.

Contractor

Assistant Engineer