PONDICHERRY UNIVERSITY **ENGINEERING WING**

Er.N.SANKARAMOURTHY, B.E.,

EXECUTIVE ENGINEER

No.PU/EW/NIQ/2017-18/

Date: 03.10.2017

NOTICE INVITING QUOTATIONS

For and on behalf of Pondicherry University the Executive Engineer, Pondicherry

University invites sealed quotations from the eligible / working contractors for the work

of "Special repairs to HRDC building". The rates should be filled in the schedule

enclosed with this and placed in a sealed cover by superscribing the name of the work in

the cover as mentioned above. An amount of Rs.1,500/- has to be furnished towards

EMD which shall be in the form of demand draft from any of the nationalized banks

payable at Pondicherry, drawn in favour of the Finance officer, Pondicherry University.

The NIQ may also be downloaded from the University web site www.pondiuni.edu.in

The filled in quotations shall be placed in the tender box kept in the reception

counter at Dr.B.R.Ambedhkar Administrative Block, Pondicherry University. The

quotations will be received up to 3.00 p.m. on 13.10.2017 and will be opened at

3.30 p.m. on the same day in the presence of tenderers those who present at the time of

opening.

The Executive Engineer, Pondicherry University reserves the right to accept or

reject any or all quotations without assigning any reason thereof.

EXECUTIVE ENGINEER

Encl: Schedule

PONDICHERRY UNIVERSITY ENGINEERING WING

SCHEDULE OF WORK

Name of the work: Special repairs to HRDC building.

S.No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1 15.13. 1	Taking out doors, windows and clerestory window shutters (steel or wood) including stacking within 50m lead - Of area 3 sq. metre and below.	10.00		Each	
2 14.1.1	Repairs to plaster of thickness 12mm to 20mm in patches of area 2.5 sq. metres and under including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete including disposal of rubbish to the dumping ground within 50 metres lead - With cement mortar 1:4 (1 cement: 4 fine sand)	5.00		Sqm	
3 9.20.1	Providing and fixing ISI marked flush door shutters conforming to IS:2202 (Part 1) decorative type, core of block board construction with frame of 1 st class hard wood and well matched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters. 35mm thick including ISI marked stainless steel butt hinges with necessary screws.	12.00		Sqm	
4 9.124	Providing and fixing 28mm thick door shutter made of solid PVC foam profile with homogenous fine cellular structure having smooth outer integral skin having 71mm width & 28mm thick as vertical & horizontal styles. Joints are made using solvent adhesive and GI 'C sections (39mm x 19mm x 0.6mm thick) or MS pipe (40mm x 20mm) stiffener frame insert & telescopic polymeric 'L' corners. The panel shall be filled with 3mm thick	5.00		Sqm	

	high – pressure compact laminate as per			
	manufacturer's specifications . Cover			
	moulding shall be provided for covering			
	fixing screws and elegant look. (For W.C.			
	bathroom door shutter)			
5	Providing and fixing PVC rigid foam	21.00	Sqm	
9.125	sheet 1mm thick on existing door shutters			
	(Bathroom and WC doors) using synthetic			
	rubber based adhesive			
6	Renewing glass panes, with putty and	4.00	Sqm	
14.5.2	nails wherever necessary - Float glass		•	
	panes of thickness 5mm.			
7	Painting with oil type wood preservative	35.00	Sqm	
13.57.	of approved brand and manufacture -		1	
1	New work (Two or more coats)			
8	Applying priming coat - with ready mixed	35.00	Sqm	
13.50.	aluminium primer of approved brand and			
2	manufacture on resinous wood and			
	plywood.			
9	Painting with synthetic enamel paint of	35.00	Sqm	
13.62.	approved brand and manufacture of		•	
1	required colour to give an even shade -			
	Two or more coats on new work over an			
	under coat of suitable shade with ordinary			
	paint of approved brand and manufacture.			
10	Wall painting with plastic emulsion paint	18.00	Sqm	
13.60.	- Royal of approved brand and		1	
1A	manufacture to give an even shade - two			
	or more coats on new work			
	Total			

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 20 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.

Contractor

Executive Engineer