PONDICHERRY UNIVERSITY **ENGINEERING WING**

Er.N.SANKARAMOURTHY, B.E.,

EXECUTIVE ENGINEER

No.PU/EW/NIQ/2017-18/

Date: 06.07.2017

NOTICE INVITING QUOTATIONS

For and on behalf of Pondicherry University, Executive Engineer, Engineering

wing, Pondicherry University invites sealed quotations from the eligible contractors

for the work of "Repair work to the D-25, E-10, F-30, F-35, D-5 and C-8 quarters

building". The rates should be filled in the schedule enclosed with this and placed in a

sealed cover by superscribing the name of the work in the cover as mentioned above.

An amount of Rs.1,350/- has to be furnished towards EMD which shall be in the form

of demand draft from any one of the nationalized banks payable at Pondicherry, drawn

in favour of the Finance officer, Pondicherry University. The notice with schedule can

also be downloaded from the University website. www.pondiuni.edu.in

The filled in quotation shall to be placed in the tender box kept in the reception

counter at Dr.B.R.Ambedhkar Administrative Block, Pondicherry University. The

quotations will be received up to 3.00 p.m. on 19.07.2017 and will be opened at 3.30

p.m. on the same day in the presence of tenderers those who present at the time of

opening.

The Executive Engineer, Engineering wing, Pondicherry University reserves

the right to accept or reject any or all quotation without assigning any reason thereof.

EXECUTIVE ENGINEER

Encl: Schedule

PONDICHERRY UNIVERSITY ENGINEERING WING

SCHEDULE OF WORK

<u>Name of the work:</u> Repair work to the D-25, E-10, F-30, F-35, D-5 and C-8 quarters building.

| S.No. | Description | Qty. | Rate Rs.P. | Unit | Amount Rs.P. |
|-------------------|--|-------|---------------|------|--------------|
| 1 15.13. 1 | Taking out doors, windows and clerestory window shutters (steel or wood) including stacking within 50m lead - of area 3 sq. metre and below. | 6 Nos | | Each | |
| 2 9.1.2P | Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position - Padak wood | 0.050 | | Cum | |
| 3 9.9.1.2 P | Providing and fixing glazed shutters for doors, windows and clerestory windows using4mm thick float glass panes including black enamelled ISI marked MS butt hinges with necessary screws Padak teak wood -30mm thick | 3.00 | | Sqm | |
| 4 9.9.1.1 P | Providing and fixing glazed shutters for doors, windows and clerestory windows using 4 mm thick float glass panes including black enamelled ISI marked MS butt hinges with necessary screws. Padak wood - 35mm thick | 2.00 | | Sqm | |
| 5 9.97.4 | Providing and fixing aluminium tower bolts ISI marked anodised (anodic coating not less than grade AC 10 as per IS:1868) transparent or dyed to required colour or shade with necessary screws etc. complete : - 150x10mm | 8 Nos | | Each | |
| 6 9.96.2 | Providing and fixing aluminium sliding door bolts ISI marked anodised (anodic coating not less than grade AC 10 as per IS:1868) transparent or dyed to required colour or shade with nuts and screws etc. complete:-250x16mm | 2 Nos | | Each | |

| 7 9.20.2 | Providing and fixing ISI marked flush door shutters conforming to IS:2202 (Part 1) decorative type, core of block board construction with frame of 1 st class hard wood and well matched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters 30mm thick including ISI marked stainless steel butt hinges with necessary screws | 2.00 | Sqm |
|-------------------|--|-------|------|
| 8 9.100. 1 | Providing and fixing aluminium handles ISI marked anodised (anodic coating not less than grade AC 10 as per IS:1868) transparent or dyed to required colour or shade with necessary screws etc.complete :-125mm | 5 Nos | Each |
| 9 9.53 | Providing 40x5 mm flat iron hold fast 40cm long including fixing to frame with 10mm diameter bolts, nuts and wooden plugs and embedding in cement concrete block 30x10x15cm 1:3:6 mix (1 cement : 3 coarse sand : 6 graded stone aggregate 20mm nominal size) | 6 Nos | Each |
| 10 9.96.2 | Providing and fixing aluminium sliding door bolts ISI marked anodised (anodic coating not less than grade AC 10 as per IS:1868) transparent or dyed to required colour or shade with nuts and screws etc.complete:-250x16mm | 1 No | Each |
| 11 A.R | Replastering or finishing the damaged cutting portion of the door wall wherever required including paint finish etc. | 1 Job | Job |
| 12 15.23. 1 | Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50m lead - For thickness of tiles above 10mm and upto 25mm. | 5.00 | Sqm |
| 13 11.38 | Providing and laying ceramic glazed floor tiles 300x300 mm (thickness to be specified by the manufacturer) of first quality conforming to IS: 15622 of approved make (Bell / Johnson / Regency / Somany / Naveen / Asian) in all colors, shades, except white, ivory, grey, fume red | 5.00 | Sqm |

| | | | <u> </u> | |
|-------------------|--|-------|----------|--|
| | brown laid on 20mm thick bed of cement mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement and matching pigments etc., complete. | | | |
| 14 17.13. 2 | Providing and fixing white vitreous china water closet squatting pan (Indian type) Orissa pattern WC pan of size 580 x 440mm. | 1 No | Each | |
| 15 17.14. 1 | Extra for using coloured WC pan instead of white WC pan Orissa pattern WC pan 580 x 440 mm. | 1 No | Each | |
| 16 15.2.2 | Demolishing cement concrete manually / by mechanical means including disposal ofmaterial within 50 metres lead - 1:4:8 or leaner mix. | 0.50 | Cum | |
| 17 4.1.10 | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering All work upto plinth level -1:5:10 (1 cement:5coarse sand : 10 graded stone aggregate 40mm nominal size) | 0.50 | Cum | |
| 18 10.27 | Supplying and fixing of steel grill work of m. s. angles, flats, squares and pipes including cost of welding charges, fixing in position in masonry walls with cement concrete 1:2:4 (1 cement : 2 course sand : 4 graded stone aggregate 12.5mm nominal size) including one coat of priming coat etc. complete. | 185 | Kg | |
| 19 14.6.1 | Renewing glass panes, with wooden fillets wherever necessary –Float glass panes of thickness 4mm. | 0.50 | Sqm | |
| 20 M.R | Supplying and fixing of nylon rope of 2.50mm dia etc. | 80.00 | Mt. | |
| 21 13.61. 1 | Painting with synthetic enamel paint of approved brand and manufacture to give an even shade - Two or more coats on new work. | 9.00 | Sqm | |
| 22 4.1.3 | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering All work upto plinth level -1:2:4 (1 cement:2coarse | 0.10 | Cum | |

| | sand: 4 graded stone aggregate 20mm | | | |
|--------|--|------|------|--|
| | nominal size) | | | |
| 23 | Demolishing brick work, manually / by | 0.10 | Cum | |
| 15.7.4 | mechanical means including stacking of | | | |
| | serviceable material and disposal of | | | |
| | unserviceable material within 50 metres | | | |
| | lead - In cement mortar. | | | |
| 24 | Providing and laying pvc pipe complete | 5 | Mt. | |
| A.R | with pvc fittings including trenching and | | | |
| | re-filling etc., for external work of 110mm | | | |
| | dia (6kg/Sqm) nominal bore. The rate | | | |
| | include cost of material and labour charges | | | |
| | etc., complete | | | |
| 25 | Providing and laying pvc pipe complete | 5 | Mt. | |
| A.R | with pvc fittings including trenching and | | | |
| | refilling etc., for external work of 90mm | | | |
| | dia (6kg/sqcm) nominal bore. The rate | | | |
| | include cost of all material and labour | | | |
| 26 | charge etc., | 2 | | |
| 26 | Providing and fixing pvc trap of 110mm | 2 | Each | |
| A.R | dia including cost of cutting and making | | | |
| | good the walls and floors with necessary | | | |
| | stiff cement concrete etc., The rate include | | | |
| | cost of material and labour charges etc., | | | |
| | complete | | | |
| | Total | | | |

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 30 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) Vat @ 3.5% will be deducted from the bill.

Contractor

Executive Engineer