

PONDICHERRY UNIVERSITY
ENGINEERING WING

Er.N.SANKARAMOURTHY, B.E.,
EXECUTIVE ENGINEER

No.PU/EW/NIQ/2017-18/

Date: 07.11.2017

NOTICE INVITING QUOTATIONS

For and on behalf of Pondicherry University, Executive Engineer, Engineering wing, Pondicherry University invites sealed quotations from the eligible / working contractors for the work of “Replacing the damaged flooring tiles at room no:33 and first floor dormitory and other repair works in Ganga hostel building”. The rates should be filled in the schedule enclosed with this and placed in a sealed cover by superscribing the name of the work in the cover as mentioned above. An amount of Rs.950/- has to be furnished towards EMD which shall be in the form of demand draft from any one of the nationalized banks payable at Pondicherry, drawn in favour of the Finance officer, Pondicherry University. The notice with schedule can also be downloaded from the University website. www.pondiuni.edu.in

The filled in quotation shall to be placed in the tender box kept in the reception counter at Dr.B.R.Ambedhkar Administrative Block, Pondicherry University. The quotations will be received up to 3.00 p.m. on 15.11.2017 and will be opened at 3.30 p.m. on the same day in the presence of tenderers those who present at the time of opening.

The Executive Engineer, Engineering wing, Pondicherry University reserves the right to accept or reject any or all quotation without assigning any reason thereof.

EXECUTIVE ENGINEER

Encl: Schedule

PONDICHERY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of work: Replacing the damaged flooring tiles at room no:33 and first floor dormitory and other repair works in Ganga hostel building.

Sl. No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1 15.23 .1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50m lead - For thickness of tiles above 10mm and upto 25mm.	27		Sqm	
2 11.38	Providing and laying ceramic glazed floor tiles 300x300 mm (thickness to be specified by the manufacturer) of first quality conforming to IS: 15622 of approved make (Bell / Johnson / Regency / Somany / Naveen / Asian) in all colors, shades, except white, ivory, grey, fume red brown laid on 20mm thick bed of cement mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement and matching pigments etc., complete.	27		Sqm	
3 10.5. 1	Providing and fixing 1mm thick M.S. sheet door with frame of 40X40X6mm angle iron and 3mm M.S. gusset plates at the junctions and corners, all necessary fittings complete, including applying a priming coat of approved steel primer. Using M.S. angles 40X40X6mm for diagonal braces.	2		Sqm	
4 15.7. 4	Demolishing brick work, manually / by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead - In cement mortar.	1		Cum	
5 17.73 .2	Providing and fixing PTMT towel rail complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality and colour 600mm long towel rail with total length of	10		Each	

	645mm, width 78mm and effective height of 88mm, weighing not less than 190gm.				
6 13.61 .1	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade - Two or more coats on new work.	5		Sqm	
7 AR	Providing and fixing netlon mesh of approved quality an the existing window opening by using welfro. The rate include cost of materials and labour charges etc.	16		Sqm	
8 AR	Replastering or finishing the damaged cutting portion of the door side wall wherever required including paint finish etc.	1		Job	
9 15.13 .1	Taking out doors, windows and clerestory window shutters (steel or wood) including stacking within 50m lead - Of area 3 sq. metre and below.	1		Each	
10 14.6. 1	Renewing glass panes, with wooden fillets wherever necessary - Float glass panes of thickness 4mm.	2		Sqm	
	Total				

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 15 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.

EXECUTIVE ENGINEER