PONDICHERRY UNIVERSITY ENGINEERING WING

Er.N.SANKARAMOURTHY, B.E.,

EXECUTIVE ENGINEER

No.PU/EW/NIQ/2017-18/

Date: 03.10.2017

NOTICE INVITING QUOTATIONS

For and on behalf of Pondicherry University the Executive Engineer,

Pondicherry University invites sealed quotations from the eligible / working

contractors for the work of "Replacement of worned out Main Gate – I (IN & OUT)".

The rates should be filled in the schedule enclosed with this and placed in a sealed

cover by superscribing the name of the work in the cover as mentioned above. An

amount of Rs.3,300/- has to be furnished towards EMD which shall be in the form of

demand draft from any of the nationalized banks payable at Pondicherry, drawn in

favour of the Finance officer, Pondicherry University. The NIQ may also be

downloaded from the University web site www.pondiuni.edu.in

The filled in quotations shall be placed in the tender box kept in the reception

counter at Dr.B.R.Ambedhkar Administrative Block, Pondicherry University. The

quotations will be received up to 3.00 p.m. on 13.10.2017 and will be opened at

3.30 p.m. on the same day in the presence of tenderers those who present at the time

of opening.

The Executive Engineer, Pondicherry University reserves the right to accept or

reject any or all quotations without assigning any reason thereof.

EXECUTIVE ENGINEER

Encl: Schedule

PONDICHERRY UNIVERSITY ENGINEERING WING

SCHEDULE OF WORK

Name of the work: Replacement of worned out Main Gate – I (IN & OUT)

S.No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1 10.27	Supplying and fixing of steel grill work of m.s. angles,flats,squares and pipes including cost of welding charges, fixing in position in masonry walls with cement concrete 1:2:4 (1 cement : 2 course sand : 4 graded stone aggregate 12.5mm nnominalsize) including one coat of priming coat etc. complete.	1550.00		Kg	
2 13.61. 1	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade - Two or more coats on new work.	50.00		Sqm	
3 15.18	Dismantling steel work in built up sections in angles, tees, flats and channels including all gusset plates, bolts, nuts, cutting rivets, welding etc. including dismembering and stacking within 50 metre lead.	1750.00		Kg	
4 13.47. 1	Sale of dismantled steel gate at in main gate No:II, the amount will be recovered from the bill on actual weight basics.	1750.00		Kg	
5 2.6	Dismantling of cement concrete pavements by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 cum in volume and stock pilling at designated locations and disposal of dismantled materials upto a lead of 1000 metres, stacking serviceable and unserviceable materials separately.	6.00		Cum	
6 11.7	Cement concrete pavement with 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size) including finishing	6.00		Cum	

	complete.			
7	Wall painting with plastic emulsion	30.00	sqm	
14.53.	paint - Commercial of approved			
1C	brand and manufacture to give an			
	even shade - One or more coats on			
	old work			
	Total			

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 30 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.

Contractor

Executive Engineer