

PONDICHERRY UNIVERSITY
ENGINEERING WING

Er.N.SANKARAMOURTHY, B.E.,
EXECUTIVE ENGINEER

No.PU/EW/NIQ/2016-17

Date: 29.07.2016

NOTICE INVITING QUOTATIONS

For and on behalf of Pondicherry University the Executive Engineer, Pondicherry University invites sealed quotations from the eligible / working contractors for the work of "Providing false ceiling in Computer room and partition in store room at Controller of Examination building". The rates should be filled in the schedule enclosed with this and placed in a sealed cover by superscribing the name of the work in the cover as mentioned above. An amount of Rs.1,250/- has to be furnished towards EMD which shall be in the form of demand draft from any of the nationalized banks payable at Pondicherry, drawn in favour of the Finance officer, Pondicherry University. The NIQ may also be downloaded from the University web site www.pondiuni.edu.in

The filled in quotations shall to be placed in the tender box kept in the reception counter at Dr.B.R.Ambedhkar Administrative Block, Pondicherry University. The quotations will be received up to 3.00 p.m. on 12.08.2016 and will be opened at 3.30 p.m. on the same day in the presence of tenderers those who present at the time of opening.

The Executive Engineer, Pondicherry University reserves the right to accept or reject any or all quotations without assigning any reason thereof.

EXECUTIVE ENGINEER

PONDICHERRY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of the work: Providing false ceiling in Computer room and partition in store room at Controller of Examination building

S.No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1 12.45. 1	Providing and fixing at all height false ceiling including providing and fixing of frame work made of special sections power pressed from M.S. sheet and galvanised in accordance with zinc coating of grade 350 as per IS :277 and consisting of angle cleats of size 25mm wide X 1.6mm thick with flanges of 22mm and 37mm at 1200mm centre to centre one flange fixed to ceiling with dash fastener 12.5mm dia X 40mm long with 6mm dia bolts to the angle hangers of 25X25X0.55mm of required length, and other end of angle hanger being fixed with nut and bolts to the G.I. channels 45X15X0.9mm running at the rate of 1200mm centre to centre to which the ceiling section 0.5mm thick bottom wedge of 80mm with tapered flanges of 26mm each having clips of 10.5mm at 450mm centre to centre shall be fixed in a direction perpendicular to G.I. channel with connecting clips made out of 2.64mm dia X 230mm long G.I. wire at every junction including fixing the gypsum board with ceiling section and perimeter channels 0.5mm thick 27mm high having flanges of 20mm and 30mm long, the perimeter of ceiling fixed to wall / partition with the help of rawl plugs at 450mm centre to centre with 25mm long drive-all screws @ 230mm interval including jointing and fixing to a flush finish of tapered and square edges of the board	26		Sqm	

	with recommended filler, jointing tapes, finisher and two coats of primer suitable for board as per manufactures specification and also including the cost of making openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitable fixed all complete as per drawing and specification but excluding the cost of painting with : 12.5mm thick tapered edge gypsym board conforming to IS: 2095 - part I,				
2 13.60. 1C	Wall painting with plastic emulsion paint - Commercial of approved brand and manufacture to give an even shade - two or more coats on new work	26		Sqm	
3 21.1.1 .1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections / appropriate Z sections and other sections of approved make conforming to IS : 733 and IS : 1285, fixed with rawl plugs and screws or with fixing clips, or with expansion hold fasteners including necessary filling up of gaps at junctions, at top, bottom and sides with required PVC / neoprene felt etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / panelling, C.P. brass / stainless steel screws, all complete as per architectural drawings. (Glazing and panelling to be paid for separately) : For fixed portion. Anodised aluminium (anodised transparent or dyed to required shade according to IS : 1868, Minimum anodic coating of grade AC 15)	46		Kg	
4 21.2.1	Providing and fixing 9mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS :	17		Sqm	

	12823 grade 1 type II in panneling fixed in aluminimum doors, windows, shutters and partition frames with C.P. brass / stainless steel screws etc., complete as per architectural drawings. Prelaminated particle board with decorative lamination on one side and balancing lamination on other side.				
	Total				

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 1 month.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) VAT @ 3.5% will be deducted from the bill.

Contractor

Executive Engineer