

PONDICHERRY UNIVERSITY
ENGINEERING WING

Er.N.SANKARAMOURTHY, B.E.,
EXECUTIVE ENGINEER

No.PU/EW/NIQ/2017-18

Date: 08.06.2017

NOTICE INVITING QUOTATIONS

For and on behalf of Pondicherry University the Executive Engineer, Pondicherry University invites sealed quotations from the eligible / working contractors for the work of “Special repairs and Maintenance to auditorium and open auditorium at School of Tamil”. The rates should be filled in the schedule enclosed with this and placed in a sealed cover by superscribing the name of the work in the cover as mentioned above. An amount of Rs.1,500/- has to be furnished towards EMD which shall be in the form of demand draft from any of the nationalized banks payable at Pondicherry, drawn in favour of the Finance officer, Pondicherry University. The NIQ may also be downloaded from the University web site www.pondiuni.edu.in

The filled in quotations shall be placed in the tender box kept in the reception counter at Dr.B.R.Ambedhkar Administrative Block, Pondicherry University. The quotations will be received up to 3.00 p.m. on 21.06.2017 and will be opened at 3.30 p.m. on the same day in the presence of tenderers those who present at the time of opening.

The Executive Engineer, Pondicherry University reserves the right to accept or reject any or all quotations without assigning any reason thereof.

EXECUTIVE ENGINEER

Encl: Schedule

PONDICHERRY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of the work: Special repairs and Maintenance to auditorium and open auditorium at School of Tamil

S.No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1 14.17	Raking out joints in lime or cement mortar and preparing the surface for re-pointing or replastering including disposal of rubbish to the dumping ground within 50 metres lead.	125		Sqm	
2 13.34	Raised and cut pointing on stone work in white cement mortar 1:3 (1 white cement : 3 marble dust).	125		Sqm	
3 14.43	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	210		Sqm	
4 13.47. 1	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade - New work (Two or more coats applied @ 1.43 ltr / 10 sqm over and including base coat of water proofing cement paint applied @ 2.20 kg/10 sqm).	210		Sqm	
	Total				

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 30 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) VAT @ 3.5% will be deducted from the bill.

Contractor

Executive Engineer