

PONDICHERRY UNIVERSITY
ENGINEERING WING

Er.N.SANKARAMOURTHY, B.E.,
EXECUTIVE ENGINEER

No.PU/EW/NIQ/2017-18/

Date: 13.07.2017

NOTICE INVITING QUOTATIONS (SECOND CALL)

For and on behalf of Pondicherry University, Executive Engineer, Engineering wing, Pondicherry University invites sealed quotations from the eligible contractors for the work of “Replacing the damaged pressed clay tiles at terrace roof of D-29 staff quarters building”. The rates should be filled in the schedule enclosed with this and placed in a sealed cover by superscribing the name of the work in the cover as mentioned above. An amount of Rs.1,500/- has to be furnished towards EMD which shall be in the form of demand draft from any one of the nationalized banks payable at Pondicherry, drawn in favour of the Finance officer, Pondicherry University. The notice with schedule can also be downloaded from the University web site www.pondiuni.edu.in and submitted

The filled in quotation shall to be placed in the tender box kept in the reception counter at Dr.B.R.Ambedhkar Administrative Block, Pondicherry University. The quotations will be received up to 3.00 p.m. on 25.07.2017 and will be opened at 3.30 p.m. on the same day in the presence of tenderers those who present at the time of opening.

The Executive Engineer, Engineering wing, Pondicherry University reserves the right to accept or reject any or all quotation without assigning any reason thereof.

EXECUTIVE ENGINEER

Encl: Schedule

PONDICHERRY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of the work: Replacing the damaged pressed clay tiles at terrace roof of D-29 staff quarters building

S.No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1 15.23. 1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50m lead - For thickness of tiles above 10mm and upto 25mm	95		Sqm	
2 12.20	Providing and laying pressed clay tiles (as per approved pattern 18mm nominal thickness and of approved size) on roofs jointed with cement mortar 1:4 (1 cement : 4 coarse sand) mixed with 2% intergral water proofing compound laid over a bed of 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) and finished neat complete.	95		Sqm	
3 10.27	Supplying and fixing of steel grill work of m.s. angles, flats, squares and pipes including cost of welding charges, fixing in position in masonry walls with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 12.5mm nominal size) including one coat of priming coat etc. complete.	48		Kg	
4 AR	Providing and fixing GI sheet of thickness gauge 0.60mm. The rate includes the cost of material, welding charges, grinding etc., complete with neat finish as directed by the Engineer-in-charge	2		Sqm	
5 13.61. 1	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade - Two or more coats on new work	2		Sqm	
	Total				

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 30 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) VAT @ 3.5% will be deducted from the bill.

Contractor

Executive Engineer