PONDICHERRY UNIVERSITY

ENGINEERING WING

Er.N.SANKARAMOURTHY, B.E.,

EXECUTIVE ENGINEER

No.PU/EW/NIQ/2017-18/

Date: 07.02.2018

NOTICE INVITING QUOTATIONS

For and on behalf of Pondicherry University, Executive Engineer, Engineering

wing, Pondicherry University invites sealed quotations from the eligible contractors

for the work of "Replacing the damaged wooden frames and shutter for doors at E-14

quarters building". The rates should be filled in the schedule enclosed with this and

placed in a sealed cover by superscribing the name of the work in the cover as

mentioned above. An amount of Rs.1,200/- has to be furnished towards EMD which

shall be in the form of demand draft from any one of the nationalized banks payable at

Pondicherry, drawn in favour of the Finance officer, Pondicherry University. The

notice with schedule can also be downloaded from the University website.

www.pondiuni.edu.in

The filled in quotation shall to be placed in the tender box kept in the reception

counter at Dr.B.R.Ambedhkar Administrative Block, Pondicherry University. The

quotations will be received up to 3.00 p.m. on 20.02.2018 and will be opened at 3.30

p.m. on the same day in the presence of tenderers those who present at the time of

opening.

The Executive Engineer, Engineering wing, Pondicherry University reserves

the right to accept or reject any or all quotation without assigning any reason thereof.

EXECUTIVE ENGINEER

Encl: Schedule

PONDICHERRY UNIVERSITY ENGINEERING WING

SCHEDULE OF WORK

Name of the work: Replacing the damaged wooden frames and shutter for doors at E-14 quarters building

S. No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1 15.1 2.1	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 m lead – Of area 3 sq. metres and below.	2	10.1	Each	1012 1
2 15.1 3.1	Taking out doors, windows and clerestory window shutters (steel or wood) including stacking within 50m lead - Of area 3 sq. metre and below.	1		Each	
3 9.1.2 P	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position - Padak wood	0.150		Cum	
4	Replastering and finishing the damaged cutting portion of the door wall wherever required including paint finish etc.	1		Job	
5 9.53	Providing 40x5 mm flat iron hold fast 40cm diameter bolts, nuts and wooden plugs and embedding in cement concrete block 30x10x15cm 1:3:6 mix (1 cement : 3 coarse sand : 6 graded stone aggregate 20mm nominal size)	12		Each	
6 9.10 0.1	Providing and fixing aluminium handles ISI marked anodised (anodic coating not less than grade AC 10 as per IS:1868) transparent or dyed to required colour or shade with necessary screws etc.complete :-125mm	4		Each	
7 9.97. 3	Providing and fixing aluminium tower bolts ISI marked anodised (anodic coating not less than grade AC 10 as per IS:1868) transparent or dyed to required colour or shade with necessary screws etc.complete: - 200x10mm	2		Each	

8 9.5.1 .1P	Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows including ISI marked black enamelled M.S butt hinges with necessary screws excluding panelling which will be paid for separately Padak wood - 35mm thick shutters.	5	Sqm	
9 14.6.	Renewing glass panes, with wooden fillets wherever necessary - Float glass panes of thickness 6mm	1	Sqm	
10 13.5 0.1	Applying priming coat - with ready mixed pink or grey primer of approved brand and manufacture on wood work (hard and soft wood).	13	Sqm	
11 13.6 1.1	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade - Two or more coats on new work.	13	Sqm	
12 9.7.1 P	Providing and fixing panelling or paneling and glazing in panelled or panelled and glazed shutters for doors, windows and clerestory windows (area of opening for panel inserts excluding portion inside grooves or rebates to be measured). Panelling for panelled or panelled and glazed shutters 25mm to 40mm thick: Padak wood	5	Sqm	
	Total			

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 20 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.

Executive Engineer