PONDICHERRY UNIVERSITY ENGINEERING WING

Er.N.SANKARAMOURTHY, B.E., EXECUTIVE ENGINEER

No.PU/EW/NIQ/2016-17/

Date: 06.10.2016

NOTICE INVITING QUOTATIONS

For and on behalf of Pondicherry University, Executive Engineer, Engineering wing, Pondicherry University invites sealed quotations from the eligible firm / working contractors for the work of "Providing entrance porch, annual maintenance & special repairs to the Animal house building". The rates should be filled in the schedule enclosed with this and placed in a sealed cover by superscribing the name of the work in the cover as mentioned above. An amount of Rs.3,150/- has to be furnished towards EMD which shall be in the form of demand draft from any one of the nationalized banks payable at Pondicherry, drawn in favour of the Finance officer, Pondicherry University. The notice with schedule can also be downloaded from the University web site www.pondiuni.edu.in and submitted.

The filled in quotation shall to be placed in the tender box kept in the reception counter at Dr.B.R.Ambedhkar Administrative Block, Pondicherry University. The quotations will be received up to 3.00 p.m. on 18.10.2016 and will be opened at 3.30 p.m. on the same day in the presence of tenderers those who present at the time of opening.

The Executive Engineer, Engineering wing, Pondicherry University reserves the right to accept or reject any or all quotation without assigning any reason thereof.

EXECUTIVE ENGINEER

Encl: Schedule

PONDICHERRY UNIVERSITY ENGINEERING WING

SCHEDULE OF WORK

<u>Name of the work:</u> Providing entrance porch, annual maintenance & special repairs to the Animal house building

S.No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1	Code No.14.43				
	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	80.00		Sqm	
2	Code no.2.31				
	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth upto 30 cm measured at a height of 1 m above ground level and removal of rubbish upto a distance of 50 m outside the periphery of the area cleared.	115.00		Sqm	
3	Code no.15.56				
	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50m lead.	26.00		Sqm	
4	Code No :15.7.4				
	Demolishing brick work, manually / by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead - In cement mortar.	0.50		Cum	
5	Code No :15.2.1				
	Demolishing cement concrete manually / by mechanical means including disposal of material within 50 metres lead - 1:3:6 or richer mix.	0.75		Cum	
6	Code no:2.8.1				
	Earth work in excavation by mechanical means (Hydraulic	1.50		Cum	

	excavator)/manual means in			
	foundation trenches or drains (not			
	exceeding 1.5m in width or 10 sqm			
	on plan) including dressing of sides			
	and ramming of bottoms, lift upto			
	1.5m, including getting out the			
	excavated soil and disposal of			
	surplus excavated soil as directed,			
	within a lead of 50m -All kinds of			
	soil			
7	Code no:4.1.10			
-	Providing and laying in position	1.50	Cum	
	cement concrete of specified grade	1.50	Culli	
	excluding the cost of centering and			
	č			
	shuttering All work upto plinth			
	level -1:5:10 (1 cement:5coarse sand			
	: 10 graded stone aggregate 40mm			
	nominal size)			
8	Code no:4.1.3			
	Providing and laying in position	2.50	Cum	
	cement concrete of specified grade			
	excluding the cost of centering and			
	shuttering All work upto plinth			
	level -1:2:4 (1 cement:2coarse sand :			
	4 graded stone aggregate 20mm			
	nominal size)			
9	Code No :13.6.2			
	20 mm cement plaster of mix 1:6 (1	50.00	Sqm	
	cement : 6 coarse sand)		1	
10	Code No:14.54.1			
	Painting with synthetic enamel paint	10.00	Sqm	
	approved brand and manufacture of			
	required colour to give an even			
	shade - One or more coats on old			
	work.			
11	Code No:14.66.1		 	
	Finishing walls with Acrylic Smooth	370	Sqm	
	with silicone additives exterior paint		-	
	of required shade - Old work (Two			
	or more coats applied @ 1.67 lts/10			
12	Code no:10.16.1			
	Steel work in built up tubular trusses	560.00	Kg	
	including cutting, hoisting fixing in	2 2 3 . 0 3	0	
	position and applying a priming coat			
	of approved steel primer welded and			
	bolted including special shaped			
	oonen mennumz special shapen			

				1
	washers etc. complete. Hot finished			
	welded type tubes.			
13	Code no:10.19			
	Providing and fixing M.S. round	10.00	Kg	
	holding down with nuts and washer			
	plates completes.			
14	Code no:M.R.			
	Additional labours charges for	18.00	Rmt	
	making the required curved shape			
	pipe in the roof truss work (50mm).			
15	Code no:13.61.1.			
	Painting with synthetic enamel paint	16.00	Sqm	
	of approved brand and manufacture			
	to give an even shade - Two or more			
	coats on new work.			
16	Code no:12.70			
	Providing and fixing colour coated	48.00	Sqm	
	galvalume sheet of 550 M.P.A yield			
	of AZ 150 strength formed as per			
	patterned steel rib profile with the			
	depth of 31mm pitch of 250mm and			
	overall width of 1060mm and			
	thickness 0.5mm with required J or			
	C hook bolts and nets 8mm dia G.S			
	paint and working etc., complete			
	excluding the cost of purlin , rafter			
	and truss etc.,			
	Total			

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 30 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) VAT @ 3.5% will be deducted from the bill.

Contractor

Executive Engineer