

**PONDICHERRY UNIVERSITY**  
**ENGINEERING WING**

**Er.N.SANKARAMOURTHY, B.E.,**  
EXECUTIVE ENGINEER

No.PU/EW/NIQ/2017-18/

Date: 11.10.2017

**NOTICE INVITING QUOTATIONS**

For and on behalf of Pondicherry University, Executive Engineer, Engineering wing, Pondicherry University invites sealed quotations from the eligible contractors for the work of “Convert the room in Ground floor of the Academic block as Seminar hall at Pondicherry University, Karaikal campus.” The rates should be filled in the schedule enclosed with this and placed in a sealed cover by superscribing the name of the work in the cover as mentioned above. An amount of Rs.1,550/- has to be furnished towards EMD which shall be in the form of demand draft from any one of the nationalized banks payable at Pondicherry, drawn in favour of the Finance officer, Pondicherry University. The notice with schedule can also be downloaded from the University website. [www.pondiuni.edu.in](http://www.pondiuni.edu.in)

The filled in quotation shall to be placed in the tender box kept in the reception counter at Dr.B.R.Ambedhkar Administrative Block, Pondicherry University. The quotations will be received up to 3.00 p.m. on 24.10.2017 and will be opened at 3.30 p.m. on the same day in the presence of tenderers those who present at the time of opening.

The Executive Engineer, Engineering wing, Pondicherry University reserves the right to accept or reject any or all quotation without assigning any reason thereof.

**EXECUTIVE ENGINEER**

**Encl: Schedule**

**PONDICHERRY UNIVERSITY**  
**ENGINEERING WING**

**SCHEDULE OF WORK**

*Name of the work:* Convert the room in Ground floor of the Academic block as Seminar hall at Pondicherry University, Karaikal campus.

<b>S.No.</b>	<b>Description</b>	<b>Qty.</b>	<b>Rate Rs.P.</b>	<b>Unit</b>	<b>Amount Rs.P.</b>
1 15.7.4	Demolishing brick work, manually / by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead - In cement mortar.	5		cum	
2 13.5.1	15mm cement plaster on rough side of single or half brick wall of mix - 1:4 (1 cement : 4 coarse sand)	21		sqm	
3 15.23. 1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50m lead - For thickness of tiles above 10mm and upto 25mm.	14		sqm	
4 6.1.2	Brick work with FPS bricks of class designation 35 in foundation and plinth in cement mortar 1:6 (1 cement : 6 coarse sand)	1		cum	
5 4.1.10	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering.- All work upto plinth level -1:5:10 (1 cement:5coarse sand : 10 graded stone aggregate 40mm nominal size)	5		cum	
6 11.3.1	Cement concrete flooring 1:2:4 (1 cement :2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete. 40mm thick with 20mm nominal size stone aggregate.	14		Sqm	
7 11.13. 1	Providing and fixing glass strips in joints of terrazo/ cement concrete floors. 40mm wide and 4mm thick.	27		metre	

8 11.53. 3	Providing and fixing homogeneous Polyvinyl chloride sheet in flooring and skirting in approved pattern on a smooth and damp proof base using rubber based adhesives of approved quality including rolling with light wooden roller weighing about 5kg. All complete - 2mm thick – sheet	17		sqm	
9 14.43	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	125		sqm	
10 13.43. 1	Applying one coat of cement primer of approved brand and manufacture on wall surface - Cement primer	125		sqm	
11 13.60. 1C	Wall painting with plastic emulsion paint - Commercial of approved brand and manufacture to give an even shade - two or more coats on new work	205		sqm	
	<b>Total</b>				

**Terms & Conditions:**

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 30 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.

**Executive Engineer**