

PONDICHERRY UNIVERSITY
ENGINEERING WING

Er.N.SANKARAMOURTHY, B.E.,
EXECUTIVE ENGINEER

No.PU/EW/NIQ/2016-17/

Date: 17.11.2016

NOTICE INVITING QUOTATIONS

For and on behalf of Pondicherry University, Executive Engineer, Engineering wing, Pondicherry University invites sealed quotations from the eligible contractors for the work of “Replacing the damaged pressed clay tiles at terrace roof in E-9 staff quarters building”. The rates should be filled in the schedule enclosed with this and placed in a sealed cover by superscribing the name of the work in the cover as mentioned above. An amount of Rs.1,200/- has to be furnished towards EMD which shall be in the form of demand draft from any one of the nationalized banks payable at Pondicherry, drawn in favour of the Finance officer, Pondicherry University. The notice with schedule can also be downloaded from the University web site www.pondiuni.edu.in and submitted

The filled in quotation shall to be placed in the tender box kept in the reception counter at Dr.B.R.Ambedhkar Administrative Block, Pondicherry University. The quotations will be received up to 3.00 p.m. on 28.11.2016 and will be opened at 3.30 p.m. on the same day in the presence of tenderers those who present at the time of opening.

The Executive Engineer, Engineering wing, Pondicherry University reserves the right to accept or reject any or all quotation without assigning any reason thereof.

EXECUTIVE ENGINEER

Encl: Schedule

PONDICHERRY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of the work: Replacing the damaged pressed clay tiles at terrace roof in E-9 staff quarters building

S.No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1 15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50m lead.	23		sqm	
2 13.6.1	20 mm cement plaster of mix 1 :4 (1 cement: 4 coarse sand)	23		Sqm	
3 13.43. 1	Applying one coat of cement primer of approved brand and manufacture on wall surface - Cement primer	23		sqm	
4 13.47. 1	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade - New work (Two or more coats applied @ 1.43 ltr / 10 sqm over and including base coat of water proofing cement paint applied @ 2.20 kg/10 sqm).	23		Sqm	
5 15.23. 1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50m lead - For thickness of tiles above 10mm and upto 25mm	32		Sqm	
6 MR	Extra lead to dispose the dismantled and demolished materials to far away distance as directed by the Engineer-in-charge	6		Cum	
7 15.1	Demolishing lime concrete manually / by mechanical means and disposal of material within 50 metres lead.	6		Cum	

8 12.20	Providing and laying pressed clay tiles (as per approved pattern 18mm nominal thickness and of approved size) on roofs jointed with cement mortar 1:4 (1 cement : 4 coarse sand) mixed with 2% intergral water proofing compound laid over a bed of 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) and finished neat complete.	28		Sqm	
9 AR	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering all work in super structure 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 20mm nominal size)	2		Cum	
10 11.38	Providing and laying ceramic glazed floor tiles 300x300 mm (thickness to be specified by the manufacturer) of first quality conforming to IS: 15622 of approved make (Bell / Johnson / Regency / Somany / Naveen / Asian) in all colors, shades, except white, ivory, grey, fume red brown laid on 20mm thick bed of cement mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement and matching pigments etc., complete.	4		Sqm	
11 17.13. 2	Providing and fixing white vitreous china water closet squatting pan (Indian type) Orissa pattern WC pan of size 580 x 440 mm.	1		Each	
12 17.14. 1	Extra for using coloured WC pan instead of white WC pan Orissa pattern WC pan 580 x 440 mm.	1		Each	
13 15.2.2	Demolishing cement concrete manually / by mechanical means including disposal of material within 50 metres lead - 1:4:8 or	0.60		Cum	

	leaner mix.				
14 4.1.3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering.- All work upto plinth level -1:2:4 (1 cement:2coarse sand : 4 graded stone aggregate 20mm nominal size)	0.60		Cum	
15 AR	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade two or more coats on old work	16		Sqm	
	Total				

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 30 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) VAT @ 3.5% will be deducted from the bill.

Contractor

Executive Engineer