

PONDICHERRY UNIVERSITY
ENGINEERING WING

Er.N.SANKARAMOURTHY, B.E.,
EXECUTIVE ENGINEER

No.PU/EW/NIQ/2017-18/

Date: 04.12.2017

NOTICE INVITING QUOTATIONS (SECOND CALL)

For and on behalf of Pondicherry University, Executive Engineer, Engineering wing, Pondicherry University invites sealed quotations from the eligible / working contractors for the work of “Providing cement concrete pathway to IRMS gas shed at Department of Earth Sciences building.”. The rates should be filled in the schedule enclosed with this and placed in a sealed cover by superscribing the name of the work in the cover as mentioned above. An amount of Rs.1,600/- has to be furnished towards EMD which shall be in the form of demand draft from any one of the nationalized banks payable at Pondicherry, drawn in favour of the Finance officer, Pondicherry University. The notice with schedule can also be downloaded from the University website. www.pondiuni.edu.in

The filled in quotation shall to be placed in the tender box kept in the reception counter at Dr.B.R.Ambedhkar Administrative Block, Pondicherry University. The quotations will be received up to 3.00 p.m. on 14.12.2017 and will be opened at 3.30 p.m. on the same day in the presence of tenderers those who present at the time of opening.

The Executive Engineer, Engineering wing, Pondicherry University reserves the right to accept or reject any or all quotation without assigning any reason thereof.

EXECUTIVE ENGINEER

Encl: Schedule

PONDICHERY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of the work: Providing cement concrete pathway to IRMS gas shed at Department of Earth Sciences building.

S.No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1 2.8.1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 Sqm on plan) including dressing of sides and ramming of bottoms , lift upto 1.5m, including getting out the excavated soil and disposal of surplus excavated soil as directed , within a lead of 50m -All kinds of soil	9		Cum	
2 4.1.10	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering.- All work upto plinth level -1:5:10 (1 cement:5coarse sand : 10 graded stone aggregate 40mm nominal size)	5		Cum	
3 11.3.1	Cement concrete flooring 1:2:4 (1 cement :2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete. 40mm thick with 20mm nominal size stone aggregate.	34		Sqm	
4 6.1.2	Brick work with FPS bricks of class designation 35 in foundation and plinth in cement mortar 1:6 (1 cement : 6 coarse sand)	7		Cum	
5 2.27B	Supplying and filling with red earth (excluding rock) including cost and conveyance to the work site and stacking to the departmental gauge, spreading in layers not exceeding	10		Cum	

	20cm in depth, watering and consolidation using 0.5 tonne roller , or wooden or steel rammers etc. complete for making play fields, running tracks and court yards.				
6 2.27	Supplying and filling in plinth with sand under floors including, watering, ramming consolidating and dressing complete.	3		Cum	
7 2.25	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50m and lift upto 1.5m.	4		Cum	
8 13.1.2	12mm cement plaster of mix :Cement mortar 1:6 (1 cement : 6 fine sand)	12		Sqm	
9 11.13. 1	Providing and fixing glass strips in joints of terrazo/ cement concrete floors. 40mm wide and 4mm thick.	17		Mt.	
	Total				

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 30 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.

Executive Engineer