

**PONDICHERRY UNIVERSITY**  
**ENGINEERING WING**

**Er.N.SANKARAMOURTHY, B.E.,**  
ASSISTANT ENGINEER

No.PU/EW/NIQ/2012-13

Date: 9.07.12

**NOTICE INVITING QUOTATIONS (THIRD CALL)**

For and on behalf of Pondicherry University, the Assistant Engineer, Pondicherry University invites sealed quotations from the eligible/working contractors for the work of "Repairs to the toilet of Central Library". The rates shall be quoted in the schedule attached, placed in a sealed cover superscribed the name of work in the cover as mentioned above. An amount of Rs.2,000/- shall have to be paid as EMD in the form of DD drawn in favour of Finance Officer, Pondicherry University drawn in any one of the nationalized bank payable at Puducherry. The quotation without EMD shall be summarily rejected.

The filled in quotation shall to be placed in the tender box kept in the reception counter at Dr.B.R.Ambedhkar Administrative Block, Pondicherry University. The quotations will be received up to 3.00 p.m. on 24.07.2012 and will be opened at 3.30 p.m. in the presence of tenderers those who present at the time of opening.

The Superintending Engineer, Pondicherry University reserves the right to accept or reject any or all quotation without assigning any reason thereof.

**ASSISTANT ENGINEER**

**Encl: Schedule**

**To**

**PONDICHERRY UNIVERSITY**  
**ENGINEERING WING**

**SCHEDULE OF WORK**

**Name of the work:** Repairs to the toilet of Central Library

<b>S. No.</b>	<b>Description</b>	<b>Qty.</b>	<b>Rate Rs.P.</b>	<b>Unit</b>	<b>Amount Rs.P.</b>
1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50m lead - For thickness of tiles above 10mm and upto 25mm.	19		Sqm	
2	Providing and laying ceramic glazed floor tiles 300X300mm (thickness to be specified by the manufacture) of 1st quality conforming to IS : 15622 of approved make (Bell / Johnson / Regency / Somany / Naveen / Asian ) in colours such as white, ivory, grey, fume red, brown laid on 20mm thick cement mortar 1:4(1 cement : 4 Coarse sand) including pointing the joints with white cement and matching pigment etc., complete	19		Sqm	
3	Providing and laying cement concrete in retaining walls , return walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping bed blocks , anchor blocks, plain window sills, fillets etc upto floor five level, excluding the cost of centring,shuttering and finishing:1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20mm nominal size)	3		Cum	
4	Providing and fixing water closet squatting pan (Indian type W.C.pan) with 100mm sand cast iron ,P or S trap 10 litre low level white P.V.C . Flushing cistern with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete including cutting and making good the walls and floors wherever required : Stainless steel AISI -304(18/8) Orissa pattern W.C.pan of size 585x480mm with flush pipe and integrated type foot rests.	3		Each	
5	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low	4		Each	

	level white P.V.C. flushing cistern with manually controlled device (handle lever) conforming to IS 7231, with all fittings and fixtures complete including cutting and making good the walls and floors wherever required - WC pan with ISI marked black solid plastic seat and lid.				
6	Providing and fixing on wall face unplasticised rigid PVC rain water pipes conforming to IS : 13592 type A including jointing with seal ring conforming to IS : 5382 leaving 10mm gap for thermal expansion, (i) single socketed pipes. 110mm diameter.	30		M	
7	Providing and fixing on wall face unplasticised- PVC moulded fittings / accessories for unplasticised rigid PVC rain water pipes conforming to IS : 13592 type A including jointing with seal ring conforming to IS : 5382 leaving 10mm gap for thermal expansion. Single Tee with door 110X110X110mm.	3		Each	
8	Providing and fixing on wall face unplasticised- PVC moulded fittings / accessories for unplasticised rigid PVC rain water pipes conforming to IS : 13592 type A including jointing with seal ring conforming to IS : 5382 leaving 10mm gap for thermal expansion. Bend 87.5deg. 110mm bend.	7		Each	
9	Providing and fixing 140 mm dia PVC pipe of length 60 cm including uPVC cowl 140 mm dia etc, complete.	3		Each	
10	Providing and fixing on wall face unplasticised rigid PVC rain water pipes conforming to IS : 13592 type A including jointing with seal ring conforming to IS : 5382 leaving 10mm gap for thermal expansion, (i) single socketed pipes. 75mm diameter.	20		M	
11	Providing and fixing PVC 110x75 floor trap	6		Each	
12	Providing and fixing on wall face unplasticised- PVC moulded fittings / accessories for unplasticised rigid PVC rain water pipes conforming to IS : 13592 type A including jointing with seal ring conforming to IS : 5382 leaving 10mm gap for thermal expansion. Single Tee with door 75X75X75mm.	2		Each	

13	Providing and fixing on wall face unplasticised- PVC moulded fittings / accessories for unplasticised rigid PVC rain water pipes conforming to IS : 13592 type A including jointing with seal ring conforming to IS : 5382 leaving 10mm gap for thermal expansion. Bend 87.5deg. 75mm bend.	8		Each	
14	Providing and fixing PTMT bib cock of approved quality and colour 15mm nominal bore, 122mm long weighing not less than 99 gms.	5		Each	
15	Providing and fixing 50mm dia PVC pipe 4 kgf/sqcm for waste pipe	6		M	
16	Providing and fixing 50mm PVC bend	10		Each	
17	Providing and fixing 50mm PVC "T"	5		Each	
18	Providing and fixing unplasticised - PVC pipe clips of approved design to unplasticised - PVC rain water pipes by means of 50x50x50mm hard wood plugs, screwed with M.S. screws of required length including cutting brick work and fixing in cement mortar 1:4(1 cement : 4 coarse sand) and making good the wall etc. complete. 75mm	30		Each	
19	Providing and fixing unplasticised - PVC clips of approved design to unplasticised - PVC rain water pipes by means of 50x50x50mm hard wood plugs, screwed with M.S. screws of required length including cutting brick work and fixing in cement mortar 1:4(1 cement : 4 coarse sand) and making good the wall etc. complete. 110mm	30		Each	
	<b>Total</b>				

**Terms & Conditions:**

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within a period of 20 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) VAT @ 2.80% will be deducted from the bill.

**Contractor**

**Assistant Engineer**