

PONDICHERRY UNIVERSITY
ENGINEERING WING

Er.N.SANKARAMOURTHY, B.E.,
EXECUTIVE ENGINEER

No.PU/EW/NIQ/2017-18/

Date: 14.09.2017

NOTICE INVITING QUOTATIONS

For and on behalf of Pondicherry University, Executive Engineer, Engineering wing, Pondicherry University invites sealed quotations from the eligible contractors for the work of “Replacing the Damaged flooring tiles at room no: FF12 & FF14 and painting the Guest house rooms and Meeting hall of the Administrative block in Pondicherry University Karaikal campus.”. The rates should be filled in the schedule enclosed with this and placed in a sealed cover by superscribing the name of the work in the cover as mentioned above. An amount of Rs.3,650/- has to be furnished towards EMD which shall be in the form of demand draft from any one of the nationalized banks payable at Pondicherry, drawn in favour of the Finance officer, Pondicherry University. The notice with schedule can also be downloaded from the University website. www.pondiuni.edu.in

The filled in quotation shall to be placed in the tender box kept in the reception counter at Dr.B.R.Ambedhkar Administrative Block, Pondicherry University. The quotations will be received up to 3.00 p.m. on 26.09.2017 and will be opened at 3.30 p.m. on the same day in the presence of tenderers those who present at the time of opening.

The Executive Engineer, Engineering wing, Pondicherry University reserves the right to accept or reject any or all quotation without assigning any reason thereof.

EXECUTIVE ENGINEER

Encl: Schedule

PONDICHERRY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of the work: Replacing the Damaged flooring tiles at room no: FF12 & FF14 and painting the Guest house rooms and Meeting hall of the Administrative block in Pondicherry University Karaikal campus.

S.No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1 15.23. 1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50m lead - For thickness of tiles above 10mm and upto 25mm.	79		sqm	
2 11.41. 2A	Providing and laying fully vitrified floor tiles of size 60x60cm (thickness to be specified by the manufacturer) with water absorption's less than 0.08% and conforming to IS: 15622 of approved make (Nitco / Rak / Johnson / Asian) in all colors and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 600x600mm.	79		sqm	
3 14.43	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	425		sqm	
4 13.43. 1	Applying one coat of cement primer of approved brand and manufacture on wall surface - Cement primer	425		sqm	
5 13.60. 1C	Wall painting with plastic emulsion paint - Commercial of approved brand and manufacture to give an even shade - two or more coats on new work	425		sqm	
	Total				

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 30 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.

Contractor

Executive Engineer