

PONDICHERRY UNIVERSITY
ENGINEERING WING

Er.N.SANKARAMOURTHY, B.E.,
EXECUTIVE ENGINEER
No.PU/EW/NIQ/2017-18/

Date: 18.08.2017

NOTICE INVITING QUOTATIONS (SECOND CALL)

For and on behalf of Pondicherry University, Executive Engineer, Engineering wing, Pondicherry University invites sealed quotations from the eligible contractors for the work of “Providing brick partition and dismantling the existing aluminium partition at Department of Microbiology, S.B. - I”. The rates should be filled in the schedule enclosed with this and placed in a sealed cover by superscribing the name of the work in the cover as mentioned above. An amount of Rs.1,100/- has to be furnished towards EMD which shall be in the form of demand draft from any one of the nationalized banks payable at Pondicherry, drawn in favour of the Finance officer, Pondicherry University. The notice with schedule can also be downloaded from the University web site www.pondiuni.edu.in and submitted

The filled in quotation shall to be placed in the tender box kept in the reception counter at Dr.B.R.Ambedhkar Administrative Block, Pondicherry University. The quotations will be received up to 3.00 p.m. on 31.08.2017 and will be opened at 3.30 p.m. on the same day in the presence of tenderers those who present at the time of opening.

The Executive Engineer, Engineering wing, Pondicherry University reserves the right to accept or reject any or all quotation without assigning any reason thereof.

EXECUTIVE ENGINEER

Encl: Schedule

PONDICHERRY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of the work: Providing brick partition and dismantling the existing aluminium partition at Department of Microbiology, S.B. - I

S.No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1	Code No: 15.57				
	Dismantling aluminium / Gypsum partitions, doors, windows, fixed glazing and false ceiling including disposal of unserviceable surplus material and stacking of serviceable material within 50m lead.	39.00		Sqm	
2	Code No: 15.23.2				
	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50m lead -For thickness of tiles above 25mm and upto 40mm	2.00		Sqm	
3	Code No:15.56				
	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50m lead.	8.00		Sqm	
4	Code No: 6.4.2				
	Brick work with FPS bricks of class designation 35 in superstructure above plinth level upto floor V level in all shapes and sizes in cement mortar 1:6 (1 cement : 6 coarse sand)	4.50		Cum	
5	Code No: 13.1.1				
	12mm cement plaster of mix :Cement mortar 1:4 (1 cement : 4 fine sand)	21.00		Sqm	
6	Code No: 13.3.2				
	20mm cement plaster of mix cement mortar 1:6 (1 cement : 6 fine sand)	20.00		Sqm	
7	Code No: 13.26A				
	Providing and applying ready mixed wall putty (JK / BIRLA) of 2mm thickness over plastered surface to	39.00		Sqm	

	prepare the surface even and smooth complete				
8	Code No: 13.41.1				
	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade - New work (two or more coats) over and including priming coat with cement primer.	39.00		Sqm	
9	Code No: 14.45.1				
	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade -Old work (one or more coats)	100		Sqm	
10	Code No: 14.42.1				
	White washing with lime to give aneven shade -Old work (two or more coats).	5.00		Sqm	
11	Code No: MR				
	Supplying and fixing fleeted screens at Dept. of Microbiology using the approved quality screen cloth width not less than 48" with necessary curtain rod (rainbow) curtain rings and fittings, screen cloth used should be not less than Rs.140/ per mt. The rate including all labours and materials etc., complete as per the direction of the Engineer-in-charge.				
	a) Handloom material	15.00		Rmt	
	b) Handloom lining	15.00		Rmt	
	c) Stretching charge	7.00		Part	
	d) Curtain rod rainbow	13.00		Feet	
	e) Rod fixing charge	2.00		Each	
	Total				

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 30 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) VAT @ 3.5% will be deducted from the bill.

Contractor

Executive Engineer