

PONDICHERRY UNIVERSITY
ENGINEERING WING

Er.N.SANKARAMOURTHY, B.E.,
EXECUTIVE ENGINEER

No.PU/EW/NIQ/2017-18/

Date: 05.01.2018

NOTICE INVITING QUOTATIONS

For and on behalf of Pondicherry University, Executive Engineer, Engineering wing, Pondicherry University invites sealed quotations from the eligible contractors / reputed firms for the work of “Replacing the damaged vertical (standing) wooden side drop on the stage of Auditorium at Guest house-I building”. The rates should be filled in the schedule enclosed with this and placed in a sealed cover by superscribing the name of the work in the cover as mentioned above. An amount of Rs.3,700/- has to be furnished towards EMD which shall be in the form of demand draft from any one of the nationalized banks payable at Pondicherry, drawn in favour of the Finance officer, Pondicherry University. The notice with schedule can also be downloaded from the University website. www.pondiuni.edu.in

The filled in quotation shall to be placed in the tender box kept in the reception counter at Dr.B.R.Ambedhkar Administrative Block, Pondicherry University. The quotations will be received up to 3.00 p.m. on 19.01.2018 and will be opened at 3.30 p.m. on the same day in the presence of tenderers those who present at the time of opening.

The Executive Engineer, Engineering wing, Pondicherry University reserves the right to accept or reject any or all quotation without assigning any reason thereof.

EXECUTIVE ENGINEER

Encl: Schedule

PONDICHERY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of the work: Replacing the damaged vertical (standing) wooden side drop on the stage of Auditorium at Guest house-I building.

S. No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1 12.6 4A	Providing, supplying and fixing panels of aluminium composite panel cladding in required design and design in metallic colour of approved shade made out of 3mm thick aluminium composite panel material consisting of 2mm thick FR grade mineral core sandwiched between two aluminium sheet (each 0.5 thick). The aluminium composite panel cladding sheet shall be coil coated with Kynar 500 based PVDF / Lumiflon based fluoropolymer resin coating of approved colour and shade on face No:1 and polymer (service) coating on face No:2 as specified and the panels shall be fixed on the structural frame of anodized aluminium extruded sections of size 38mm x28mm (weighing approximately @0.490kg/m) placed suitably at not less than 60 cm centre to centre and fitted with the wall using G.I angles of size 38mm x38mm x100mm , through aluminium cleat angles and fastened using stainless steel screws , bolts and nuts etc and the 6mm thick joint gaps / grooves shall be filled with aluminium / translucent / grey / black / clear or white weather Silican Sealant. The rate is inclusive of all materials , labour charges, erection, scaffolding charges and other standard accessories etc. – For external walls surfaces for all floors.	54		sqm	
	Total				

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 20 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.

Executive Engineer