

PONDICHERRY UNIVERSITY
ENGINEERING WING

Er.N.SANKARAMOURTHY, B.E.,
EXECUTIVE ENGINEER

No.PU/EW/NIQ/2017-18/

Date: 05.01.2018

NOTICE INVITING QUOTATIONS

For and on behalf of Pondicherry University, Executive Engineer, Engineering wing, Pondicherry University invites sealed quotations from the eligible / working contractors for the work of “Repair works at Mother Theresa Mess building”. The rates should be filled in the schedule enclosed with this and placed in a sealed cover by superscribing the name of the work in the cover as mentioned above. An amount of Rs.2,600/- has to be furnished towards EMD which shall be in the form of demand draft from any one of the nationalized banks payable at Pondicherry, drawn in favour of the Finance officer, Pondicherry University. The notice with schedule can also be downloaded from the University website. www.pondiuni.edu.in

The filled in quotation shall to be placed in the tender box kept in the reception counter at Dr.B.R.Ambedhkar Administrative Block, Pondicherry University. The quotations will be received up to 3.00 p.m. on 19.01.2018 and will be opened at 3.30 p.m. on the same day in the presence of tenderers those who present at the time of opening.

The Executive Engineer, Engineering wing, Pondicherry University reserves the right to accept or reject any or all quotation without assigning any reason thereof.

EXECUTIVE ENGINEER

Encl: Schedule

PONDICHERY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of the work: Repair works at Mother Theresa Mess building.

S. No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1 15.2 3.2	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50m lead - For thickness of tiles above 25mm and upto 40mm.	32		Sqm	
2 15.2 5	Dismantling stone slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50m lead.	40		Sqm	
3 11.2 6.1	Kota stone slab flooring over 20mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab including rubbing and polishing complete with base of cement mortar 1:4 (1 cement : 4 coarse sand). 25mm thick.	40		Sqm	
4 11.4 1.4B	Providing and laying fully vitrified floor tiles of size 100X100cm (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622 of approved make (Nitco / Rak / Johnson / Asian) in all colors and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 1000x1000mm. (Commercial quality)	8		Sqm	
5 11.3 7	Providing and laying ceramic glazed floor tiles 300X300mm (thickness to be specified by the manufacture) of 1st quality conforming to IS : 15622	25		Sqm	

	of approved make (Bell / Johnson / Regency / Somany / Naveen / Asian) in colours such as white, ivory, grey, fume red, brown laid on 20mm thick cement mortar 1:4(1 cement : 4 Coarse sand) including pointing the joints with white cement and matching pigment etc., complete				
6 6.1.2	Brick work with FPS bricks of class designation 35 in foundation and plinth in cement mortar 1:6 (1 cement : 6 coarse sand)	0.50		Cum	
7 4.1.3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering.- All work upto plinth level -1:2:4 (1 cement:2coarse sand : 4 graded stone aggregate 20mm nominal size)	5		Cum	
8 13.2. 2	15mm cement plaster on the rough side of single or half brick wall of mix: cement mortar 1:6 (1 cement : 6 fine sand)	2		Sqm	
9 13.5 0.3	Applying priming coat: with ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanized iron/steel works.	15		sqm	
10 13.6 1.1	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade - Two or more coats on new work	15		Sqm	
	Total				

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 20 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.

Executive Engineer