

PONDICHERRY UNIVERSITY
ENGINEERING WING

Er.N.SANKARAMOURTHY, B.E.,
EXECUTIVE ENGINEER

No.PU/EW/NIQ/2017-18/

Date: 24.08.2017

NOTICE INVITING QUOTATIONS

For and on behalf of Pondicherry University, Executive Engineer, Engineering wing, Pondicherry University invites sealed quotations from the eligible contractors for the work of “Repair works at Yamuna hostel building”. The rates should be filled in the schedule enclosed with this and placed in a sealed cover by superscribing the name of the work in the cover as mentioned above. An amount of Rs.2,550/- has to be furnished towards EMD which shall be in the form of demand draft from any one of the nationalized banks payable at Pondicherry, drawn in favour of the Finance officer, Pondicherry University. The notice with schedule can also be downloaded from the University website. www.pondiuni.edu.in

The filled in quotation shall to be placed in the tender box kept in the reception counter at Dr.B.R.Ambedhkar Administrative Block, Pondicherry University. The quotations will be received up to 3.00 p.m. on 05.09.2017 and will be opened at 3.30 p.m. on the same day in the presence of tenderers those who present at the time of opening.

The Executive Engineer, Engineering wing, Pondicherry University reserves the right to accept or reject any or all quotation without assigning any reason thereof.

EXECUTIVE ENGINEER

Encl: Schedule

PONDICHERY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of the work: Repair works at Yamuna hostel building.

S.No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1 17.18. 1	Providing and fixing PVC low level flushing cistern with manually controlled device (handle lever) conforming to IS 7231 with all fittings and fixtures complete – 10 litre capacity white.	6		Each	
2 18.64	Providing and fixing PTMT swivelling shower, 15 mm nominal bore, weighing not less than 40 grams.	4		Each	
3 17.28. 2.1	Providing and fixing PVC waste pipe for sink or wash basin including PVC waste fittings complete - Flexible pipe - 32mm dia.	18		Each	
4 17.13. 2	Providing and fixing white vitreous china water closet squatting pan (Indian type) Orissa pattern WC pan of size 580 x 440mm.	5		Each	
5 17.73. 2	Providing and fixing PTMT towel rail complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality and colour 600mm long towel rail with total length of 645mm, width 78mm and effective height of 88mm, weighing not less than 190	18		Each	
6 9.1.2P	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position - Padak wood	0.04		Cum	
7 13.61. 1	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade - Two or more coats on new work.	2.00		Sqm	

8 17.7.4	Providing and fixing wash basin with CI brackets, 15mm CP brass pillar taps 32 mm CP brass waste of standard pattern including painting of fittings and brackets, cutting and making good the walls wherever required White vitreous china flat back wash basin size 550x400mm with single 15mm CP brass pillar taps.	3		Each	
9 17.69. 2	Providing and fixing PTMT waste coupling for wash basin and sink, of approved quality and colour waste coupling 38 mm of 83 mm length and 77 mm breadth weighing not less than 60 gm.	3		Each	
10 18.9.1 2	Providing and fixing ASTM pipes including all ASTM plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00m spacing. This includes jointing of pipes & fitting with one step ASTM solvent cement and testing of joints complete (Internal work exposed on wall) - 25mm nominal outer dia pipes	72.00		Mt.	
11 18.9.1 5	Providing and fixing ASTM pipes including all ASTM plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00m spacing. This includes jointing of pipes & fitting with one step ASTM solvent cement and testing of joints complete (Internal work exposed on wall) - 50mm nominal outer dia pipes	15.00		Mt.	
12 15.23. 1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50m lead - For thickness of tiles above 10mm and upto 25mm.	8.00		Sqm	
13 11.37	Providing and laying ceramic glazed floor tiles 300X300mm (thickness to be specified by the manufacture) of 1st quality conforming to IS : 15622 of	8.00		Sqm	

	approved make (Bell / Johnson / Regency / Somany / Naveen / Asian) in colours such as white, ivory, grey, fume red, brown laid on 20mm thick cement mortar 1:4(1 cement : 4 Coarse sand) including pointing the joints with white cement and matching pigment etc., complete				
14 A.R	Providing and laying pvc pipe complete with pvc fittings including trenching or refilling etc, for external work of 110mm dia nominal bore. The rate include cost of material and labour charges etc complete.	20.00		Mt.	
15 12.41. 2	Providing and fixing on wall face unplasticised rigid PVC rain water pipes conforming to IS : 13592 type A including jointing with seal ring conforming to IS : 5382 leaving 10mm gap for thermal expansion, (i) single socketed pipes. 110mm diameter.	84.00		Mt.	
16 12.42. 3.2	Providing and fixing on wall face unplasticised- PVC moulded fittings / accessories for unplasticised rigid PVC rain water pipes conforming to IS : 13592 type A including jointing with seal ring conforming to IS : 5382 leaving 10mm gap for thermal expansion. Single Tee with door 110X110X110mm.	14		Each	
17 12.43. 2	Providing and fixing unplasticised - PVC clips of approved design to unplasticised - PVC rain water pipes by means of 50x50x50mm hard wood plugs, screwed with M.S. screws of required length including cutting brick work and fixing in cement mortar 1:4(1 cement : 4 coarse sand) and making good the wall etc. complete. 110mm	56		Each	
18 12.42. 5.1	Providing and fixing on wall face unplasticised- PVC moulded fittings / accessories for unplasticised rigid	7		Each	

	PVC rain water pipes conforming to IS : 13592 type A including jointing with seal ring conforming to IS : 5382 leaving 10mm gap for thermal expansion. Bend 87.5deg. 75mm bend.				
19 15.2.2	Demolishing cement concrete manually / by cum mechanical means including disposal of material within 50 metres lead - 1:4:8 or leaner mix.	2.00		Cum	
20 4.1.10	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering.- All work upto plinth level -1:5:10 (1 cement:5coarse sand : 10 graded stone aggregate 40mm nominal size)	2.00		Cum	
21 A.R	Providing and fixing ASTM valve of approved quality – 50mm dia nominal bore.	1		Each	
22 A.R	Providing and fixing ASTM valve of approved quality – 20mm dia nominal bore.	18		Each	
23 M.R	Dismantling the GI pips and clamps including stacking the material within 50M lead – 15 mm to 50mm dia.	87.00		Mt.	
	Total				

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 30 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) VAT @ 3.5% will be deducted from the bill.

Contractor

Executive Engineer