

PONDICHERRY UNIVERSITY
ENGINEERING WING

Er.N.SANKARAMOURTHY, B.E.,
EXECUTIVE ENGINEER

No.PU/EW/NIQ/2016-17

Date: 27.12.2016

NOTICE INVITING QUOTATIONS

For and on behalf of Pondicherry University the Executive Engineer, Pondicherry University invites sealed quotations from the eligible / working contractors for the work of "Replacing the damaged water line and replacing of damaged wooden door frames at Department of Physical Education". The rates should be filled in the schedule enclosed with this and placed in a sealed cover by superscribing the name of the work in the cover as mentioned above. An amount of Rs.1,800/- has to be furnished towards EMD which shall be in the form of demand draft from any of the nationalized banks payable at Pondicherry, drawn in favour of the Finance officer, Pondicherry University. The NIQ may also be downloaded from the University web site www.pondiuni.edu.in

The filled in quotations shall to be placed in the tender box kept in the reception counter at Dr.B.R.Ambedhkar Administrative Block, Pondicherry University. The quotations will be received up to 3.00 p.m. on 11.01.2017 and will be opened at 3.30 p.m. on the same day in the presence of tenderers those who present at the time of opening.

The Executive Engineer, Pondicherry University reserves the right to accept or reject any or all quotations without assigning any reason thereof.

EXECUTIVE ENGINEER

Encl: Schedule

**PONDICHERRY UNIVERSITY
ENGINEERING WING**

SCHEDULE OF WORK

Name of work: Replacing the damaged water line and replacing of damaged wooden door frames at Department of Physical Education

Sl. no	Description	Qty	Rate Rs.P.	Unit	Amount Rs.P.
1. 9.84	Providing and fixing IS:3564 make aluminium extruded section body tubular type universal hydraulic door closer with double speed adjustment with necessary accessories and screws etc. complete	2		Each	
2 18.9.33	Providing and fixing ASTM pipes including all ASTM plain & brass threaded fittings this included jointing of pipes & fittings with one step ASTM solvent cement, trenching refilling & testing of joints Complete (External work) - 32mm nominal outer dia pipes	116		M	
3 18.9.11	Providing and fixing ASTM pipes including all ASTM plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00m spacing. This includes jointing of pipes & fitting with one step ASTM solvent cement and testing of joints complete (Internal work exposed on wall) - 20mm nominal outer dia pipes	40		M	
4 18.63	Providing and fixing PTMT angle stop cock 15 mm nominal bore, weighing not less than 85 grams.	21		each	
5 18.56.1	Providing and fixing PTMT pillar cock of approved quality and colour 15mm nominal bore, 107mm long, weighing not less than 110 grams.	11		Each	
6 17.31	Providing and fixing 600x450mm bevelled number edge mirror of superior glass (of approved quality) complete with 6mm thick hard board ground fixed to wooden cleats with C.P brass screws and washers complete.	7		No.	
7 15.12.1	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete	8		each	

	and stacking within 50 m lead – Of area 3 sq. metres and below.				
8 17.13.2	Providing and fixing white vitreous china water closet squatting pan (Indian type) Orissa pattern WC pan of size 580 x 440 mm.	1		Each	
9 14.40.2	Providing and fixing chromium plated brass butt hinges with necessary screws etc. complete - 100x70x4mm (Ordinary type)	24		Each	
10 11.36D	Providing and fixing commercial quality ceramic glazed wall tiles conforming to IS : 15622 (thickness to be specified by the manufacture of approved make (Jhonson / Asian / Somany / Nitco) in all colours, shades of size 200 x 300 mm as approved in skirting, risers of steps and dados over 12mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3 kg per sqm. Including pointing in white cement mixed with pigment of matching shade complete. - size 200x300mm	10		Sqm	
11 9.119	Providing and fixing factory made P.V.C. door frame of size 50x47mm with a wall thickness of 5mm, made out of extruded 5mm rigid PVC foam sheet mitred at corners and joined with 2nos.of 150mm long brackets of 15x15mm M.S.square tube, the vertical door profiles to be reinforced with 19x19mm M.S.square tube of 19 gauge,EDM rubber gasket weather seal to be provided through out the frame.The door frame to be fixed to the wall using M.S.screws of 65/100mm size complete as per anufacturers specification .	40		Rmt	
12 19.33.1	Providing and fixing on wall /column face unplasticed - PVC soil and waste pipes (type-B) conforming to IS:13592-1992 including jointing with seal ring conformation to IS: 5382 leaving 10mm gap for thermal expansion - single socketed pipes 110mm diameter	12		M	
13 6.18	Tile brick masonry with tile brick of class designation 35 in	1		Cum	

	superstructure above plinth level upto floor V level in cement mortar 1:6 (1 cement: 6 coarse sand)				
14 15.23.1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50m lead - For thickness of tiles above 10mm and upto 25mm	1.50		Sqm	
15 4.1.11A	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level 1:5:10 (1 cement : 5 sand : 10 graded brick aggregate 40mm nominal size).	0.50		Cum	
16 11.38.2	Providing and laying ceramic glazed floor tiles 300x300 mm (thickness to be specified by the manufacturer) of commercial quality conforming to IS: 15622 of approved make (Bell / Johnson / Regency / Somany / Naveen / Asian) in all colors, shades, except white, ivory, grey, fume red brown laid on 20mm thick bed of cement mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement and matching pigments etc., complete.	1.50		Sqm	
17 13.1.2	12mm cement plaster of mix :Cement mortar 1:6 (1 cement : 6 fine sand)	6		sqm	
	Total				

Terms & Conditions:

- i) The rate specified is firm and not subject to any variation.
- ii) The work should be completed within 30 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) VAT @ 3.5% will be deducted from the bill.

Contractor

Executive Engineer