

PONDICHERRY UNIVERSITY
ENGINEERING WING

Er.N.SANKARAMOURTHY, B.E.,
EXECUTIVE ENGINEER

No.PU/EW/NIQ/2016-17

Date: 07.02.2017

NOTICE INVITING QUOTATIONS

For and on behalf of Pondicherry University the Executive Engineer, Pondicherry University invites sealed quotations from the eligible / working contractors for the work of "Additional and alternation to the existing name board wall at Silver Jubilee campus". The rates should be filled in the schedule enclosed with this and placed in a sealed cover by superscribing the name of the work in the cover as mentioned above. An amount of Rs.3000/- has to be furnished towards EMD which shall be in the form of demand draft from any of the nationalized banks payable at Pondicherry, drawn in favour of the Finance officer, Pondicherry University. The NIQ may also be downloaded from the University web site www.pondiuni.edu.in

The filled in quotations shall to be placed in the tender box kept in the reception counter at Dr.B.R.Ambedhkar Administrative Block, Pondicherry University. The quotations will be received up to 3.00 p.m. on 16.02.2017 and will be opened at 3.30 p.m. on the same day in the presence of tenderers those who present at the time of opening.

The Executive Engineer, Pondicherry University reserves the right to accept or reject any or all quotations without assigning any reason thereof.

EXECUTIVE ENGINEER

Encl: Schedule

PONDICHERRY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of the work: Additional and alternation to the existing name board wall at Silver Jubilee campus

S.No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1	Code No: 15.23.2				
	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50m lead - For thickness of tiles above 25mm and upto 40mm.	25.00		Sqm	
2	Code No:13.3.1				
	20mm cement plaster of mix 1:4 (1cement : 4 sqm fine sand)	25.00		Sqm	
3	Code No : 14.43				
	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	43.00		Sqm	
4	Code No : 13.43.1				
	Applying one coat of cement primer of approved brand and manufacture on wall surface - Cement primer	43.00		Sqm	
5	Code no: 13.60.1A				
	Wall painting with plastic emulsion paint - Royal of approved brand and manufacture to give an even shade - two or more coats on new work	43.00		Sqm	
6	Code No:2.31				
	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth upto 30 cm measured at a height of 1 m above ground level and removal of rubbish upto a distance of 50 m outside the periphery of the area cleared.	100		Sqm	
7	Code No :8.2.2.2				
	Providing and fixing 18mm thick gang saw cut mirror polished (premoulded and prepolished)	2.00		Sqm	

	machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size of approved shade, colour and texture laid over 20mm thick base cement mortar 1:4 (1 cement: 4 coarse sand) with joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing moulding and polishing to edge to give high gloss finish etc. complete at all levels. - Granite of any colour and shade - Area of slab over 0.50 sqm				
8	Code No: 11.24				
	Extra for prefinished nosing to treads of steps of marble stone.	14.00		Rmt	
9	Code No: MR				
	Providing and fixing 1st quality ceramic glass mosaic tiles crystal series of size 25x25mm of brand Lezare. Over the plastered wall surface with matching pigment, for pointing etc., complete as direction by the Engineer – in- charge. - size 20x20mm	18.00		Sqm	
10	Code No.MR				
	Providing and fixing 18mm thick gang saw cut mirror polished (premoulded and prepolished) machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size of approved shade, colour and texture laid over 20mm thick base cement mortar 1:4 (1 cement: 4 coarse sand) with joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing moulding and polishing to edge to give high gloss finish etc. complete at all levels. - Granite of black colour of size 8'x2' slabs fixed in 3 rows, 2 columns including engraving of letters as per approved write-up to required size and font , painting the engraved	8.78		sqm	

	letters with golden/silver Paint etc., complete as per the direction of Engineer – in- charge				
	Total				

Terms & Conditions:

- i) The rate specified is firm and not subject to any variation.
- ii) The work should be completed within 30 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) VAT @ 3.5% will be deducted from the bill.

Contractor

Executive Engineer