

PONDICHERRY UNIVERSITY
ENGINEERING WING

Er.N.SANKARAMOURTHY, B.E.,
EXECUTIVE ENGINEER

No.PU/EW/NIQ/2016-17

Date: 17.03.2017

NOTICE INVITING QUOTATIONS

For and on behalf of Pondicherry University the Executive Engineer, Pondicherry University invites sealed quotations from the eligible / working contractors for the work of "Special repairs and maintenance to Amudham mess and Ilango adigal hostel". The rates should be filled in the schedule enclosed with this and placed in a sealed cover by superscribing the name of the work in the cover as mentioned above. An amount of Rs.2,800/- has to be furnished towards EMD which shall be in the form of demand draft from any of the nationalized banks payable at Pondicherry, drawn in favour of the Finance officer, Pondicherry University. The NIQ may also be downloaded from the University web site www.pondiuni.edu.in

The filled in quotations shall be placed in the tender box kept in the reception counter at Dr.B.R.Ambedhkar Administrative Block, Pondicherry University. The quotations will be received up to 3.00 p.m. on 30.03.2017 and will be opened at 3.30 p.m. on the same day in the presence of tenderers those who present at the time of opening.

The Executive Engineer, Pondicherry University reserves the right to accept or reject any or all quotations without assigning any reason thereof.

EXECUTIVE ENGINEER

Encl: Schedule

PONDICHERRY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of the work: Special repairs and maintenance to Amudham mess and Ilango adigal hostel

S.No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1 15.23. 2	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50m lead - For thickness of tiles above 25mm and upto 40mm	34		Sqm	
2 15.2.1	Demolishing cement concrete manually / by mechanical means including disposal of material within 50 metres lead - 1:3:6 or richer mix.	6		Cum	
3 4.1.2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering.- All work upto plinth level -1:11/2:3 (1 cement:1 ½ coarse sand : 3 graded stone aggregate 20mm nominal size)	2		Cum	
4 11.26. 1	Kota stone slab flooring over 20mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab including rubbing and polishing complete with base of cement mortar 1:4 (1 cement : 4 coarse sand). 25mm thick.	34		Sqm	
5 14.67. 1	Finishing walls with Premium Acrylic Smooth exterior paint of required shade - Old work (Two or more coats applied @ 1.43 lts/10 sqm) over existing cement paint surface	460		Sqm	
6 16.10 0	Acid cleaning for the existing Mosaic floors, glazed tiles work and removing the stains and decays to give a glassy look etc complete (The acid used shall be 32% concentrated hydrochloric acid after taking on the precautionary	300		Sqm	

	measures)				
7 14.54. 1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade - One or more coats on old work	64		Sqm	
8 11.4	52mm thick cement concrete flooring with concrete hardener topping under layer 40mm thick cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate of 20mm nominal size) and top layer 12mm thick cement hardener consisting of mix 1:2 (1 cement hardener mix : 2 graded stone aggregate 6mm nominal size) by volume. Hardening compound is mixed @ 2 litres per 50kg of cement or as per manufacturers specifications. This includes cost of cement slurry, but excluding the cost of nosing of steps etc. complete.	34		Sqm	
	Total				

Terms & Conditions:

- i) The rate specified is firm and not subject to any variation.
- ii) The work should be completed within 30 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) VAT @ 3.5% will be deducted from the bill.

Contractor

Executive Engineer