

PONDICHERRY UNIVERSITY
ENGINEERING WING

Er.N.SANKARAMOURTHY, B.E.,
EXECUTIVE ENGINEER

No.PU/EW/NIQ/2017-18/

Date: 20.07.2017

NOTICE INVITING QUOTATIONS

For and on behalf of Pondicherry University the Executive Engineer, Pondicherry University invites sealed quotations from the eligible / working contractors for the work of “Replacing the thermocol false ceiling at room S-7 Department of Food science Technology Laboratory”. The rates should be filled in the schedule enclosed with this and placed in a sealed cover by superscribing the name of the work in the cover as mentioned above. An amount of Rs.1,200/- has to be furnished towards EMD which shall be in the form of demand draft from any of the nationalized banks payable at Pondicherry, drawn in favour of the Finance officer, Pondicherry University. The NIQ may also be downloaded from the University web site www.pondiuni.edu.in

The filled in quotations shall be placed in the tender box kept in the reception counter at Dr.B.R.Ambedhkar Administrative Block, Pondicherry University. The quotations will be received up to 3.00 p.m. on 31.07.2017 and will be opened at 3.30 p.m. on the same day in the presence of tenderers those who present at the time of opening.

The Executive Engineer, Pondicherry University reserves the right to accept or reject any or all quotations without assigning any reason thereof.

EXECUTIVE ENGINEER

Encl: Schedule

PONDICHERY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of work: Replacing the thermocol false ceiling at room S7 Department of Food
Science Technology Laboratory

Sl. no	Description	Qty	Rate	Unit	Amount
1 15.57	Dismantling aluminium / Gypsum partitions, doors, windows, fixed glazing and false ceiling including disposal of unserviceable surplus material and stacking of serviceable material within 50m lead.	57.00		sqm	
2 12.45.1	Providing and fixing at all height false ceiling including providing and fixing of frame work made of special sections power pressed from M.S. sheet and galvanised in accordance with zinc coating of grade 350 as per IS :277 and consisting of angle cleats of size 25mm wide X 1.6mm thick with flanges of 22mm and 37mm at 1200mm centre to centre one flange fixed to ceiling with dash fastener 12.5mm dia X 40mm long with 6mm dia bolts to the angle hangers of 25X25X0.55mm of required length, and other end of anglehanger being fixed with nut and bolts to the G.I. channels 45X15X0.9mm running at the rate of 1200mm centre to centre to which the ceiling section 0.5mm thick bottom wedge of 80mm with tapered flanges of 26mm each having clips of 10.5mm at 450mm centre to centre shall be fixed in a direction perpendicular to G.I. channel with connecting clips made out of 2.64mm dia X 230mm long G.I. wire at every junction including fixing the gypsum board with ceiling section and perimeter channels 0.5mm thick 27mm high having flanges of 20mm and 30mm long, the perimeter of ceiling fixed to wall / partition with the help of rawl	57.00		sqm	

	plugs at 450mm centre to centre with 25mm long drive-all screws @ 230mm interval including jointing and fixing to a flush finish of tapered and				
3 13.60.1 A	Wall painting with plastic emulsion paint - Royal of approved brand and manufacture to give an even shade - two or more coats on new work	57.00		sqm	
	Total				

Terms & Conditions:

- i) The rate specified is firm and not subject to any variation.
- ii) The work should be completed within 10 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) VAT @ 3.5% will be deducted from the bill.

Executive Engineer