

PONDICHERRY UNIVERSITY
ENGINEERING WING

Er.N.SANKARAMOURTHY, B.E.,
EXECUTIVE ENGINEER

No.PU/EW/NIQ/2017-18/

Date: 08.12.2017

NOTICE INVITING QUOTATIONS

For and on behalf of Pondicherry University, Executive Engineer, Engineering wing, Pondicherry University invites sealed quotations from the eligible / working contractors for the work of “Providing and fixing homogeneous Polyvinyl chloride sheet flooring and false ceiling at Dr.Maheswaran Mani lab, Science Block - I”. The rates should be filled in the schedule enclosed with this and placed in a sealed cover by superscribing the name of the work in the cover as mentioned above. An amount of Rs.2,200/- has to be furnished towards EMD which shall be in the form of demand draft from any one of the nationalized banks payable at Pondicherry, drawn in favour of the Finance officer, Pondicherry University. The notice with schedule can also be downloaded from the University website. www.pondiuni.edu.in

The filled in quotation shall to be placed in the tender box kept in the reception counter at Dr.B.R.Ambedhkar Administrative Block, Pondicherry University. The quotations will be received up to 3.00 p.m. on 20.12.2017 and will be opened at 3.30 p.m. on the same day in the presence of tenderers those who present at the time of opening.

The Executive Engineer, Engineering wing, Pondicherry University reserves the right to accept or reject any or all quotation without assigning any reason thereof.

EXECUTIVE ENGINEER

Encl: Schedule

PONDICHERY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of the work: Providing and fixing homogeneous Polyvinyl chloride sheet flooring and false ceiling at Dr.Maheswaran Mani lab, Science Block - I.

S. No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1 11.5 3.3	Providing and fixing homogeneous Polyvinyl chloride sheet in flooring and skirting in approved pattern on a smooth and damp proof base using rubber based adhesives of approved quality including rolling with light wooden roller weighing about 5kg. All complete -2mm thick -sheet	56.00		Sqm	
2 12.6 2	Providing and fixing false ceiling works using superiorfire rated gypsum board of 12.5mm tk mounted on GI frame work with ceiling section of size 80x26x0.55x3660 mm spacing at 600mm c/c suspended from ceiling using hanger rods at 1200mm c/c with screw to level and line and applying one coat of primer , two coats of putty followed by and reflective paint in front of the stage area to the required shape and size , including scaffolding etc.complete as directed by the engineer -in-charge upto 6.5m height	70.00		Sqm	
3 14.4 5.1	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade - Old work (one or more coats).	72.00		Sqm	
4 14.5 4.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade - One or more coats on old work.	25.00		Sqm	

5 14.5 4.1	Manufacturing and supplying of wooden cupboard of size 1mx0.90mx0.35m as per the drawing enclosed made out of 18mm thick commercial plywood, back covered with 6mm thick commercial plywood with one shelf and two compartments. The rate including painting of one coat wooden primer and two coats of synthetic enamel paint including all materials etc., complete.	5.00		Each	
	Total				

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 30 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.

Executive Engineer