PONDICHERRY UNIVERSITY **ENGINEERING WING**

Er.N.SANKARAMOURTHY, B.E.,

EXECUTIVE ENGINEER

No.PU/EW/NIQ/2016-17/

Date: 23.01.2017

NOTICE INVITING QUOTATIONS

For and on behalf of Pondicherry University, Executive Engineer, Engineering

wing, Pondicherry University invites sealed quotations from the eligible contractors /

reputed firms for the work of "Maintenance of E-18 staff quarters building". The rates

should be filled in the schedule enclosed with this and placed in a sealed cover by

superscribing the name of the work in the cover as mentioned above. An amount of

Rs.3,400/- has to be furnished towards EMD which shall be in the form of demand draft

from any one of the nationalized banks payable at Pondicherry, drawn in favour of the

Finance officer, Pondicherry University. The notice with schedule can also be

downloaded from the University web site www.pondiuni.edu.in and submitted

The filled in quotation shall to be placed in the tender box kept in the reception

counter at Dr.B.R.Ambedhkar Administrative Block, Pondicherry University. The

quotations will be received up to 3.00 p.m. on 02.02.2017 and will be opened at 3.30 p.m.

on the same day in the presence of tenderers those who present at the time of opening.

The Executive Engineer, Engineering wing, Pondicherry University reserves the

right to accept or reject any or all quotation without assigning any reason thereof.

EXECUTIVE ENGINEER

Encl: Schedule

PONDICHERRY UNIVERSITY ENGINEERING WING

SCHEDULE OF WORK

Name of the work: Maintenance of E-18 staff quarters building

S.No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1 15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50m lead.	30		sqm	
2 13.6.1	20 mm cement plaster of mix 1 :4 (1 cement: 4 coarse sand)	30		Sqm	
3 14.43	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	61		sqm	
4 13.43. 1	Applying one coat of cement primer of approved brand and manufacture on wall surface - Cement primer	91		Sqm	
5 14.42. 2	White washing with lime to give an even shade - Old work (one or more coats).	270		sqm	
6 AR	Distempering with oil bound washable distemper of approved brand and manufacture old work (two or more coats)	290		sqm	
7 14.54. 1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade - One or more coats on old work.	230		Sqm	
8 16.100	Acid cleaning for the existing Mosaic floors, glazed tiles work and removing the stains and decays to give a glassy look etc complete (The acid used shall be 32% concentrated hydrochloric acid after taking on the	45		sqm	

	precautionary measures)		
9	Acid cleaning in the sanitary	7	Each
AR	appliances like IWC,EWC, wash	,	Zuen
	basin, Urinals and sink etc to give a		
	glassy look etc complete as directed		
	by the Engineer-in-charge.		
10	Finishing walls with Premium	30	Sqm
13.47.	Acrylic Smooth exterior paint with		~ 4
1	Silicone additives of required shade		
	- New work (Two or more coats		
	applied @ 1.43 ltr / 10 sqm over		
	and including base coat of water		
	proofing cement paint applied @		
	2.20 kg/10 sqm).		
11	Finishing walls with Premium	580	Sqm
14.67.	Acrylic Smooth exterior paint with		
1	Silicone additives of required shade		
	- Old work (two or more coats		
	applied @ 0.83 ltr/10 sqm)		
12	Supplying of water proofing	25	Kg
MR	compound for mixing cement		
	mortar as directed by the Engineer-		
	in-charge		
13	Diluting and injecting chemical	60	M
2.35.4.	emulsion for POST-		
1	CONSTRUCTIONAL anti-termite		
	treatment (excluding the cost of		
	chemical emulsion): Treatment of		
	existing masonry using chemical		
	emulsion @ one litre per hole at 300		
	mm interval including drilling holes		
	at 45 degree and plugging them with		
	cement mortar 1:2 (1 cement : 2		
	coarse sand) to the full depth of the		
	hole: With Chlorpyriphos / Lindane		
1.4	E.C. 20% with 1% concentration	10	114
14	Supplying chemical emulsion in	10	litres
2.34.1	sealed containers including delivery		
	as specified - Chlorpyriphos /		
	Lindane emulsifiable concentrate of		
15	20%.	58	Sam
16.71	Providing and fixing G.I chain link fabric fencing of required width in	30	Sqm
1671			

	mesh size 25x25mm made of G.I			
	wire of dia 3mm including			
	strengthening with 2mm dia wire or			
	nuts, bolts and washers as required			
	complete		~	
16	Supplying and applying of a smart	155	Sqm	
AR	care advanced damp proof is a fibre			
	reinforced elastomeric water			
	proofing coating for pressed clay			
	tiles at terrace roof. Applying a self			
	priming coat of AP smart care			
	advanced damp proof (diluted with			
	water in 3:1 ratio) and apply two			
	coats of AP smart care advanced			
	damp proof without dilution.			
	Achieved a forced coverage of 25			
	sq.ft./lit/coat and allow to dry for 4-			
	6 hours between coats. Before that,			
	prepare the surface by cleaning and			
	ensure that it is free of dust, oil			
	grease and loose particles etc., small			
	cracks 3mm or less should be			
	opened, cleaned and filled with AP			
	smart care advanced crack seal etc,.			
	The rate include cost of all material			
	and labour charges			
	Total			

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 60 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) VAT @ 3.5% will be deducted from the bill.

Contractor

Executive Engineer