

**PONDICHERRY UNIVERSITY**  
**ENGINEERING WING**  
**SCHEDULE OF WORK**

*Name of the work:* Replacing the damaged pressed clay tiles at terrace roof of the E-12 quarters building

Sl. No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1. 15.2 3.1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead – for thickness of tiles 10mm to 25mm	163		sqm	
2. 15.1	Demolishing lime concrete manually / by mechanical means and disposal of material within 50 metres	21		cum	
3. M.R	Extra lead to dispose the dismantled and demolished material to a far away by hiring the vehicle for transportation including labour for loading and unloading etc as directed by the Engineer-in-charge	10		trip	
4. A.R	Providing and laying in position of plain cement concrete of specified grade excluding the cost of centering and shuttering- all works in super structure- 1:2:4 ( 1cement: 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	9		cum	
5. 12.2 0	Providing and laying pressed clay tiles (as per approved pattern 18mm nominal thickness of approved size) on roofs jointed with cement mortar 1:4 (1 cement : 4 coarse sand) mixed with 2% integral water proofing compound , laid over a bed of 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) and finished neat complete	165		Sqm	
6. 13.2. 1	15mm cement plaster on the rough side of single or half brick wall of mix - 1:4 (1cement : 4 fine sand)	20		sqm	
7. A.R	Wall painting with plastic emulsion of approved brand and manufacture to give an even shade two or more coats on old work	60		Sqm	
8. 14.4 3	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scarches etc.complete	60		sqm	
9.	Applying one coat of water thinnable cement primer of approved brand and	60		sqm	

13.4 3.1	manufacturer on wall surface - water thinnable cement primer				
10. 14.6 7.1	Finishing walls with premium acrylic smooth exterior paint with silicon additives of required shade - old work (two or more coats applied @ 1.43 ltr / 10 sqm) over existing cement paint surface	60		sqm	
	<b>Total</b>				

**Terms & Conditions:**

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 30 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) The rate specified should be inclusive of GST.

**Contractor**

**Executive Engineer**