PONDICHERRY UNIVERSITY **ENGINEERING WING** 

Er.N.SANKARAMOURTHY, B.E.,

EXECUTIVE ENGINEER

No.PU/EW/NIQ/2016-17

Date: 07.12.2016

**NOTICE INVITING QUOTATIONS** 

For and on behalf of Pondicherry University the Executive Engineer,

Pondicherry University invites sealed quotations from the eligible / working

contractors for the work of "Special repairs and maintenance to the Central Library".

The rates should be filled in the schedule enclosed with this and placed in a sealed

cover by superscribing the name of the work in the cover as mentioned above. An

amount of Rs.1,200/- has to be furnished towards EMD which shall be in the form of

demand draft from any of the nationalized banks payable at Pondicherry, drawn in

favour of the Finance officer, Pondicherry University. The NIQ may also be

downloaded from the University web site www.pondiuni.edu.in

The filled in quotations shall to be placed in the tender box kept in the

reception counter at Dr.B.R.Ambedhkar Administrative Block, Pondicherry

University. The quotations will be received up to 3.00 p.m. on 19.12.2016 and will be

opened at 3.30 p.m. on the same day in the presence of tenderers those who

present at the time of opening.

The Executive Engineer, Pondicherry University reserves the right to accept

or reject any or all quotations without assigning any reason thereof.

**EXECUTIVE ENGINEER** 

**Encl: Schedule** 

## PONDICHERRY UNIVERSITY ENGINEERING WING

## SCHEDULE OF WORK

Name of work: Special repairs and maintenance to the Central Library

| Sl.no         | Description   | Qty | Rate<br>Rs.P. | Unit | Amount<br>Rs.P. |
|---------------|---|-----|---------------|------|-----------------|
| 1.<br>17.31   | Providing and fixing 600x450mm bevelled number edge mirror of superior glass (of approved quality) complete with 6mm thick hard board ground fixed to wooden cleats with C.P brass screws and washers complete.   |     | KS.F.         | No.  | KS.F.           |
| 2.<br>17.2.1  | Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern with manually controlled device (handle lever, Conforming to IS: 7231, with all fittings and fixtures complete) including cutting and making good the walls and floors wherever required. W.C pan with ISI marked white solid plastic seat and lid. |     |               | No.  |                 |
| 3.<br>15.12.1 | Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 m lead - Of area 3 sq. metres and below.  |     |               | each |                 |
| 4.<br>10.27   | Supplying and fixing of steel grill m.s. angles, flats, squares and pipes including cost of welding charges, fixing in position in masonry walls with cement concrete 1:2:4 (1 cement : 2 course sand : 4 graded stone aggregate 12.5mm nominal size) including one coat of priming coat etc. complete.   |     |               | kg   |                 |
| 5.<br>14.5.2  | Renewing glass panes, with putty and nails wherever necessary - Float glass panes of thickness 5mm.   | 1   |               | sqm  |                 |
| 6.<br>MR      | Repairs to the existing aluminimum work for doors, windows, ventilators and partitions fixed with rawl plugs and screws or with fixing clips, or with expansion hold fasteners including necessary filling up of gaps at junctions, at top, bottom and sides with required PVC / neoprene felt etc., C.P. brass / stainless steel screws, all complete as per direction of engineer in caharge.:                      | 2   |               | sqm  |                 |

| 7.<br>18.9.11  | Providing and fixing ASTM pipes including all ASTM plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00m spacing. This includes jointing of pipes & fitting with one step ASTM solvent cement and testing of joints complete (Internal work exposed on wall) - 20mm nominal outer dia pipes  | 10    | mtr  |
|----------------|---|-------|------|
| 8.<br>18.9.13  | Providing and fixing ASTM pipes including all ASTM plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00m spacing. This includes jointing of pipes & fitting with one step ASTM solvent cement and testing of joints complete (Internal work exposed on wall) - 32mm nominal outer dia pipes  | 10    | mtr  |
| 9.<br>18.63    | Providing and fixing PTMT angle stop cock 15 mm nominal bore, weighing not less than 85 grams.  | 5     | each |
| 10.<br>17.18.1 | Providing and fixing PVC low level flushing cistern with manually controlled device (handle lever) conforming to IS 7231 with all fittings and fixtures complete – 10 litre capacity white.   | 5     | each |
| 11.<br>18.74.2 | Providing and fixing unplastisised PVC connection pipe with PTMT nuts of approved quality and colour 15 mm nominal bore with 45 cm length.  | 5     | each |
| 12<br>9.21.2   | Providing and fixing ISI marked flush door shutters conforming to IS:2202 (Part 1) non-decorative type, core of block board construction with frame of 1 st class hard wood and well matched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters 30 mm thick including ISI marked stainless steel butt hinges with necessary screws |       | sqm  |
| 13<br>13.61.1  | Painting with synthetic enamel paint of approved brand and manufacture to give an even shade - Two or more coats on new work.   | 12.00 | Sqm  |
| 14.<br>13.50.1 | Applying priming coat - with ready mixed pink or grey primer of approved brand and manufacture on wood work (hard and soft wood).   | 4.50  | sqm  |
| 15.<br>12.43.2 | Providing and fixing unplasticised - PVC clips of approved design to unplasticised - PVC rain water pipes by means of   | 8     | No.  |

| 50x50x50mm hard wood plugs, screwed with M.S. screws of required length including cutting brick work and fixing in cement mortar 1:4(1 cement : 4 coarse sand) and making good the wall etc. complete. 110mm |  |  |
|--|--|--|
| Total  |  |  |

## **Terms & Conditions:**

- i) The rate specified is firm and not subject to any variation.
- ii) The work should be completed within 10 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) VAT @ 3.5% will be deducted from the bill.

Contractor

**Executive Engineer**