

PONDICHERRY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of the work: Providing mosquito proof net for the windows at all the Gents hostel

S.No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1 MR	Supplying and fixing fly proof netlon mesh of approved quality on the existing wooden / steel / aluminium window opening using Velcro. The rate includes cost of all material including stitching charge of Velcro fixing in position using staplers transport charges and labour charges etc.,	1000		Sqm	
2 9.40.2. 2P	Providing and fixing wooden moulded beading to door and window frames with iron screws , plugs and priming coat on unexposed surface etc. complete: Padak wood 50X20mm	1900		M	
3 13.61. 1	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade - Two or more coats on new work.	190		Sqm	
	Total				

I hereby abide the rules and regulations stipulated in the CPWD form no. 6 & 8.

Contractor

Executive Engineer