

PONDICHERRY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of work: Maintenance and replacement of water supply pipelines and classroom door shutters at Department of Applied Psychology, silver Jubilee campus Pondicherry University

S. No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1 18.9.16	Providing and fixing ASTM pipes including all ASTM plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00m spacing. This includes jointing of pipes & fitting with one step ASTM solvent cement and testing of joints complete (Internal work exposed on wall) - 63mm nominal outer dia pipes	20.00		Metre	
2 18.9.15	Providing and fixing ASTM pipes including all ASTM plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00m,spacing. This includes jointing of pipes & fitting with one step ASTM solvent cement and testing of joints complete (Internal work exposed on wall) - 50mm nominal outer dia pipes	10.00		metre	
3 18.9.13	Providing and fixing ASTM pipes including all ASTM plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00m spacing. This includes jointing of pipes & fitting with one step ASTM solvent cement and testing of joints complete (Internal work exposed on wall) - 32mm nominal outer dia pipes	15.00		metre	
4 18.9.12	Providing and fixing ASTM pipes including all ASTM plain& brass threaded fittings i/c fixing the pipe with clamps at 1.00m spacing . This includes jointing of pipes & fitting with one step ASTM solvent cement and testing of joints complete (Internal work exposed on wall) - 25mm nominal outer dia pipes	30.00		metre	
5	Providing and fixing gun metal gate valve with CI wheel of approved	1.00		each	

18.17.2	quality (screwed end) - 32 mm nominal bore				
6 18.17.5	Providing and fixing gun metal gate valve with C.I.wheel of approved quality (Screwed end) - 65mm nominal bore	3.00		each	
7 18.76.1	Cutting holes upto 30x30 cm in walls including making good the same with FPS bricks	5.00		hole	
8 15.44.2	Dismantling G.I. Pipes (external work) including excavation and refilling trenches after taking out the pipes manually / by mechanical means including stacking of pipes within 50m lead - Above 40mm nominal bore.	45.00		metre	
9 31.153.1D	Providing and fixing mild steel flange including bolts, nuts, rubber insertion, labour charges etc,complete-80mm dia	4.00		no	
10 9.20.1	Providing and fixing ISI marked flush door shutters conforming to IS:2202 (Part 1) decorative type, core of block board construction with frame of 1 st class hard wood and well matched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters. 35mm thick including ISI marked stainless steel butt hinges with necessary screws.	4.20		sqm	
11 13.62.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade - Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture	11.00		sqm	
12 9.97.1	Providing and fixing aluminium tower bolts , ISI marked , anodised (anodic coating not less than grade AC 10 as per IS :1868) , transparent or dyed to required colour or shade , with necessary screws etc. complete - 300 x10 mm	4.00		each	
13 9.96.1	Providing and fixing aluminium sliding door bolts ISI marked anodised (anodic coating not less than grade AC 10 as per IS:1868) transparent or dyed	1.00		each	

	to required colour or shade with nuts and screws etc.complete:- 300x16mm				
14 9.100.1	Providing and fixing aluminium handles ISI marked anodised (anodic coating not less than grade AC 10 as per IS:1868) transparent or dyed to required colour or shade with necessary screws etc.complete :- 125mm	4.00		each	
15 9.84	Providing and fixing aluminium extruded section body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564 , embossed on the body, door weight upto 36 kg to 80 kg and door width from 701 mm to 1000 mm) , with double speed adjustment with necessary accessories and screws etc. complete	1.00		each	
	Total				

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 10 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) The rate specified should be inclusive of GST.

Contractor

Executive Engineer