

**PONDICHERRY UNIVERSITY  
ELECTRICAL WING**

Schedule of Work

**Name of the Work:** Providing 3 nos. of Online UPS for new Mega Mess & Madam Curie Hostel Mess and replacing the old UPS battery in Amudam mess & Mother Theresa Mess of University Campus.

Sl. No.	Description of Items	Qty	Unit	Rate	Amount
1.	Supplying, installing, testing and commissioning of 1KVA off line Solar UPS including suitable stand. Make:Exide/Numeric/Luminous/Microtek/Amaron.	3 mtr	mtr		
2.	Supplying and fixing 12V 100AH Tubular battery suitable for online UPS. Make:Exide/Numeric/Luminous/Microtek/Amaron.	7 nos.	Each		
3.	Supplying and fixing following modular front cover plates and modular box on surface etc., as required. Make:MK/Legrand/Anchor a) 3 modular	10 nos.	Each		
4.	Supplying and fixing following modular switch/socket on the existing modular plate & switch box including connections but excluding modular plate etc., as required. a) 5/6 Amps Switch b) 15/16 Amps Switch c) 6 pin 15/16 Amp Socket outlet	12 nos. 6 nos. 6 nos.	Each Each Each		
5.	Supplying and drawing following sizes of FR PVC insulated copper conductor, single core cable in the existing surface/recessed steel/ PVC conduit as required. Make: Polycab/RR Kable. a) 3 x 2.5 sq mm b) 3 x 4 sq mm	100 mtr 20 mtr	mtr mtr		
6.	Supplying and fixing of following size of medium class PVC conduit along with accessories in surface/recess including				

	cutting the wall and making good the same in case of recessed conduit as required. a) 20 mm	100 mtr	mtr		
7.	Supplying, installing, testing and commissioning of pre wired, 1x36W surface mounted box type fluorescent fitting, complete with all accessories and tube etc., directly on ceiling/wall including connection with 1.5 sq mm FRLS PVC insulated, copper conductor single core cable and earthing etc., as required. Make: Crompton Greaves Model: DSG1214LP	12 nos.	Each		
8.	Less Buyback offer for following old tubular battery. a) 150Ah/12V battery	4 nos.	Each		
<b>Total</b>					

**Terms & Conditions:**

1. The work shall be carried out strictly in accordance with CPWD General Specifications for the Electrical works as amended up to date.
2. Prior approval of the Engineer in charge is required for all the materials to be used on works. Non- standard quality materials shall not be acceptable.
3. Bad workmanship shall not be accepted. Such work is liable for rejection and shall be rectified by the contractor at his own risk and cost.
4. Payment will be arranged after satisfactory completion of the work.
5. Amount will be arrived on the actual works done basis.
6. The work should be carried out immediately on receipts of this work order.
7. The rate for each item of work to be quoted in the enclosed schedule of work format only otherwise, the quotation in any other format is considered as invalid quotation.
8. The work should be completed within one month from the date of issue of the work order.
9. **Your quotation shall be accompanied with tender document Rs.500/- and EMD for an amount of Rs.2,500/- in the form of a DD drawn infavour of "Finance officer, Pondicherry University" payable at Pondicherry.**

**Name and signature of the Firm/  
Contractor with Seal.**

**ASSISTANT ENGINEER(E)**