

PONDICHERY UNIVERSITY

ENGINEERING WING

SCHEDULE OF WORK

Name of work: Special repairs and painting the room at Department of Management studies

S. No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1. 22.25.1	Providing and applying crystalline mortar by mixing in the ratio of 4.5 : 1 (4.5 parts crystalline mortar : 1 part water) for the treatment of faulty construction joints, cracks, tie rod holes and spalled & honeycombed surface of RCC underground structures like basement, water tanks, bridge deck etc. to ensure water tightness. The crystalline mortar shall conform to the EN 1504-3 having compressive strength Class R4 > 45 MPa and adhesive bond strength Class R3 > 1.5 MPa. The work shall be carried out all complete as per specification and the direction of the Engineer-In-Charge. The product performance shall carry guarantee for 10 years against any leakage.- For sealing cracks and faulty construction joints, routed out/making U-shape groove size 25x25mm and then primed the area with integral crystalline slurry @0.05kg/ running metre and while the surface is tacky filled the groove upto surface with crystalline mortar @1.50kg/ running metre. Once crystalline mortar is touch dry then finally applied two coats of integral crystalline slurry @0.05kg/running metre per coat.	15		Metre	
2. 22.23A	Providing & Applying polymer modified, flexible cementitious negative side waterproofing coating with elastic waterproofing polymers on interior wall plaster surface in three	16		sqm	

	coats @14.35 kg /10 sqm. One coat of self priming of cementitious waterproofing polymer(dilution with water in the ratio of 1:1) and two coats of cementitious waterproofing polymer (dilution with water in the ratio of 3:1) after scrapping and properly cleaning the surface to remove pre-existing paint film & loose particles till plaster is visible, complete in all respect as per the direction of Engineer-in-Charge.				
3. 13.46.1	Finishing walls with Acrylic Smooth exterior paint of required shade : New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)	32		Sqm	
4. 13.98.1	Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade: One or more coats on old work	50		sqm	
	Total				

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 30 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) The rate specified should be inclusive of GST.

Contractor

Executive Engineer