

PONDICHERRY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of work: Replacing the damaged portico tiles at guest house-I building

S. No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1. 11.51	Providing and laying 22mm thick factory made pre polished cement concrete flooring tiles of required colour and design over 20 mm thick cement mortar 1:4 (1 cement : 4 sand) and jointed with cement slurry mixed with an admixture of pigment to match the shade of the tile - (Endura \ Ultra \ Dazzle \ Technic)	75		sqm	
2. 15.23.1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50m lead - For thickness of tiles above 10mm and upto 25mm.	75		sqm	
3. 4.1.3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering.- All work upto plinth level -1:2:4 (1 cement:2coarse sand : 4 graded stone aggregate 20mm nominal size)	4		cum	
4. M.R	Extra lead for dispose the dismantled materials far way distance by using vehicle and labour for loading and unloading charges etc. complete as directed by the Engineer-in-charge	1		Job	
	Total				

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within a period of 10 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) The rate specified should be inclusive of GST.

Contractor

Executive Engineer