

PONDICHERY UNIVERSITY
ENGINEERING WING
SCHEDULE OF WORK

Name of the work: Replacing the damaged kota stone slab flooring at kitchen of the Madam Curie hostel

| S. No. | Description | Qty. | Rate Rs.P. | Unit | Amount Rs.P. |
|---------------------------------|---|-------------|-------------------|-------------|---------------------|
| 1. 15.2 5 | Dismantling stone slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50m lead | 26 | | Sqm | |
| 2. 4.1.1 0 | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering.- All work upto plinth level -1:5:10 (1 cement:5coarse sand : 10 graded stone aggregate 40mm nominal size) | 2 | | cum | |
| 3. 11.2 6.1 | Kota stone slab flooring over 20mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab including rubbing and polishing complete with base of cement mortar 1:4 (1 cement : 4 coarse sand). 25mm thick. | 26 | | Sqm | |
| | TOTAL | | | | |

Terms& Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within a period of 10 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) The rate specified should be inclusive of GST.

Contractor

Executive Engineer