

**PONDICHERRY UNIVERSITY**  
**ENGINEERING WING**

**SCHEDULE OF WORK**

Name of the work: Special repairs to the kalidas hostel for room no 14 ,15,19,21

<b>S. No.</b>	<b>Description</b>	<b>Qty.</b>	<b>Rate Rs.P</b>	<b>Unit</b>	<b>Amount Rs.P.</b>
1 14.46	Removing dry or oil bound distemper, water proofing cement paint and the like byscraping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	235.00		sqm	
2 13.41 .1	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade - New work (two or more coats) over and including priming coat with cement primer.	235.00		sqm	
3 14.54 .1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade - One or more coats on old work.	17.00		sqm	
	<b>Total</b>				

**Terms & Conditions:**

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 20 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.

**CONTRACTOR**

**EXECUTIVE ENGINEER**