

PONDICHERRY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of the work: Replacing the worned out GI water pipe line to ASTM
Pipe line at MAKKA, SRK and Ilango Adigal Gents Hostel

Sl.no	Description	Qty	Rate	Unit	Amount
1 18.9.12	Providing and fixing ASTM pipes including all ASTM plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00m spacing. This includes jointing of pipes & fitting with one step ASTM solvent cement and testing of joints complete (Internal work exposed on wall) - 25mm nominal outer dia pipes	672.00		Metre	
2 18.9.13	Providing and fixing ASTM pipes including all ASTM plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00m spacing. This includes jointing of pipes & fitting with one step ASTM solvent cement and testing of joints complete (Internal	160.00		Metre	
3 18.9.14	Providing and fixing ASTM pipes including all ASTM plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00m spacing. This includes jointing of pipes & fitting with one step ASTM solvent cement and testing of joints complete (Internalwork exposed on wall) - 40mm nominal outer dia pipes	480.00		Metre	
4 18.9.15	Providing and fixing ASTM pipes including all ASTM plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00m spacing. This includes jointing of pipes & fitting with one step ASTM solvent cement and testing of joints complete (Internal work exposed on wall) -	20.00		Metre	

	50mm nominal outer dia pipes				
5 18.9.16	Providing and fixing ASTM pipes including all ASTM plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00m jointing of pipes & fitting with one step ASTM solvent cement and testing of joints complete (Internal work exposed on wall) - 63mm nominal outer dia pipes	160.00		Metre	
6 18.7.4	Providing and fixing chlorinated polyvinyl chloride (CPVC) pipes having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00m spacing. This includes jointing of pipes & fitting with one step CPVC solvent cement and testing of joints complete. (Internal work exposed on wall) - 32mm nominal outer dia pipes	35.00		Metre	
7 17.25.2	Providing and fixing white vitreous china wash basin including making all connections but excluding the cost of fittings flat back wash basin of size 550 x 400mm.	5.00		Each	
8 18.54.2	Providing and fixing PTMT bib cock of approved quality and colour 15mm nominal bore, 122mm long weighing not less than 99 gms.	30.00		Each	
9 18.63	Providing and fixing PTMT angle stop cock 15 mm nominal bore, weighing not less than 85 grams.	50.00		Each	
10 18.64	Providing and fixing PTMT swivelling shower, 15 mm nominal bore, weighing not less than 40 grams	25.00		Each	
11 18.56.2	Providing and fixing PTMT pillar cock of approved quality and colour 15 mm nominal bore, 125mm long foam flow weighing not less than 120 grams.	30.00		Each	
12 18.17.3	Providing and fixing gun metal gate valve with CI wheel of approved quality (screwed end) - 40 mm	27.00		Each	

	nominal bore.				
13 18.17.4	Providing and fixing gun metal gate valve with CI wheel of approved quality (screwed end) - 50 mm nominal bore.	5.00		Each	
	Total				

Terms & Conditions:

- i) The rate specified is firm and not subject to any variation.
- ii) The work should be completed within 20 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) VAT @ 3.5% will be deducted from the bill.

Executive Engineer