

**PONDICHERRY UNIVERSITY
ENGINEERING WING**

Name of Work: Maintenance of E-11 Quarters to arrest the Leakage, painting works and D-23 maintenance works for replacement of the doors

Schedule of work

S.No	Description	Qty	Rate	Unit	Amount
1	Code no:15.23.1				
	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50m lead - For thickness of tiles above 10mm and upto 25mm.	155.00		Sqm	
2	Code no:12.20				
	Providing and laying pressed clay tiles (as per approved pattern 18mm nominal thickness and of approved size) on roofs jointed with cement mortar 1:4 (1 cement : 4 coarse sand) mixed with 2% intergral water proofing compound laid over a bed of 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) and finished neat complete.	155.00		Sqm	
3	Code no:15.56				
	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50m lead.	70.00		Sqm	
4	Code no:13.3.1				
	20mm cement plaster of mix 1:4 (1cement : 4 fine sand)	70.00		Sqm	
5	Code no:13.47.1				
	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade - New work (Two or more coats applied @ 1.43 ltr / 10 sqm over and including base coat of water proofing cement paint applied @ 2.20 kg/10 sqm).	70.00		Sqm	
6	Code no:14.67.2				
	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade - Old work (one or more coats applied @ 0.83 ltr/10 sqm)	580.00		Sqm	
7	Code no:14.45.1				
	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade - Old work (one or more coats).	290.00		Sqm	

8	Code no:14.54.1				
	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade - One or more coats on old work.	230.00		Sqm	
9	Code no:14.42.2				
	White washing with lime to give an even shade - Old work (one or more coats).	270.00		Sqm	
10	Code no:9.21.1				
	Providing and fixing ISI marked flush door shutters conforming to IS:2202 (Part 1) non-decorative type, core of block board construction with frame of 1 st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters. - 35 mm thick including ISI marked stainless steel butt hinges with necessary screws	2.00		Sqm	
11	Code no:9.9.1.2V				
	Providing and fixing glazed shutters for doors, windows and clerestory windows using 4mm thick float glass panes including black enamelled ISI marked MS butt hinges with necessary screws. - Vengai wood - 30mm thick	1.00		sqm	
12	Code no:9.97.2				
	Providing and fixing aluminium tower bolts ISI marked anodised (anodic coating not less than grade AC 10 as per IS:1868) transparent or dyed to required colour or shade with necessary screws etc.complete :- 250x10mm	4.00		Each	
13	Code no:9.100.1				
	Providing and fixing aluminium handles ISI marked anodised (anodic coating not less than grade AC 10 as per IS:1868) transparent or dyed to required colour or shade with necessary screws etc.complete :- 125mm	4.00		Each	
14	Code no:13.50.1				
	Applying priming coat - with ready mixed pink or grey primer of approved brand and manufacture on wood work (hard and soft wood).	6.00		Sqm	

15	Code no:13.61.1				
	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade - Two or more coats on new work.	6.00		Sqm	
16	Code no:12.20L				
	Lime concrete terracing on roofs of required thickness laid to fall with 25mm nominal size brick aggregate and 50% lime mortar 1:2 (1 lime putty : 2 surkhi) rammed and finished with gur and belgiri treatment complete including rounding of junctions with parapet wall complete	3.00		Cum	
17	Code no:MR				
	Supply and Apply of Dr.Fixit Heavy duty, reinforced acrylic coating, new coat for open terrace.	86.00		Sqm	
18	Code no:MR				
	Clean the surface, supply and apply of quick setting chemicals and Polysulphide sealent in the floor trap area, so as to complete seal the water leakage in the RCC slab. (Ref:Work Order No:PU/AE/W.O/2009-10/8351 dt:14.05.10)	1.00		Job	
19	Code no:MR				
	Supplying water proofing compound for mixing cement mortar as per the manufacturers recomentatin as decided by the Engineer-in-Charge	15.00		Kg	
20	Code no:MR				
	Extra lead to dispose the dismatled and demolished materials to a far away distance as directed by Engineer-in-Charge	10.00		Cum	
				Total	
I hearby abide by the rules and regulation stipulated in theCPWD form no 6 & 8					

Contractor

Assistant Engineer