

PONDICHERY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of the work: Providing anti termite treatment and replacing the termite infested wooden joineries and doors at UMISARC building.

S. No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1 15.12 .2	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 m lead – Of area beyond 3 sq. metre.	11.00		Each	
2 9.1.2 P	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position - Padak wood	0.90		Cum	
3 9.20. 1	Providing and fixing ISI marked flush door shutters conforming to IS:2202 (Part 1) decorative type, core of block board construction with frame of 1 st class hard wood and well matched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters. 35mm thick including ISI marked stainless steel butt hinges with necessary screws.	5.50		Sqm	
4 9.53	Providing 40x5 mm flat iron hold fast 40cm long including fixing to frame with 10mm diameter bolts, nuts and wooden plugs and embedding in cement concrete block 30x10x15cm 1:3:6 mix (1 cement : 3 coarse sand : 6 graded stone aggregate 20mm nominal size)	66.00		Each	
5 14.1. 1	Repairs to plaster of thickness 12mm to 20mm in patches of area 2.5 sq. metres and under . including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete including disposal of rubbish to the dumping ground within 50 metres lead - With cement mortar 1:4 (1 cement : 4 fine sand)	15.00		Sqm	

6 13.50 .1	Applying priming coat - with ready mixed pink or grey primer of approved brand and manufacture on wood work (hard and soft wood).	25.00		Sqm	
7 13.61 .1	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade - Two or more coats on new work.	25.00		Sqm	
8 13.60 .1A	Wall painting with plastic emulsion paint - Royal of approved brand and manufacture to give an even shade - two or more coats on new work	15.00		Sqm	
9 9.84	Providing and fixing IS:3564 make aluminium extruded section body tubular type universal hydraulic door closer with double speed adjustment with necessary accessories and screws etc.complete	10.00		Each	
10 2.34. 1	Supplying chemical emulsion in sealed containers including delivery as specified - Chlorpyriphos / Lindane emulsifiable concentrate of 20%.	240.00		Litres	
11 2.35. 2.1	Diluting and injecting chemical emulsion for POST-CONSTRUCTIONAL anti-termite treatment (excluding the cost of chemical emulsion): Along the external wall below concrete or masonry apron using chemical emulsion @ 2.25 litres per linear metre including drilling and plugging holes etc. - With Chlorpyriphos / Lindane E.C. 20% with 1% concentration.	500.00		Metre	
12 2.35. 4.1	Diluting and injecting chemical emulsion for POST-CONSTRUCTIONAL anti-termite treatment (excluding the cost of chemical emulsion): Treatment of existing masonry using chemical emulsion @ one litre per hole at 300 mm interval including drilling holes at 45 degree and plugging them with cement mortar 1:2 (1 cement : 2 coarse sand) to the full depth of the hole: With	810.00		Metre	

	Chlorpyriphos / Lindane E.C. 20% with 1% concentration.				
13 2.35. 5	Diluting and injecting chemical emulsion for POST-CONSTRUCTIONAL anti-termite treatment (excluding the cost of chemical emulsion): Treatment at points of contact of wood work by chemical emulsion Chlorpyriphos / Lindane (in oil or kerosene based solution) @ 0.5 litres per hole by drilling 6mm dia holes at downward angle of 45 degree at 150 mm centre to centre and sealing the same.	230		Metre	
	Total				

I hereby abide the rules and regulations stipulated in the CPWD form no. 6 & 8.

EXECUTIVE ENGINEER