PONDICHERRY UNIVERSITY ENGINEERING WING

SCHEDULE OF WORK

<u>Name of the work:</u> Supply of material at Pondicherry University, Karaikal Campus for sink a new tube well

S.No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1	UPVC 200mm dia plain casing pipe	264		Mt	
MR	conforming to IS :12818-1992				
	(outside dia 226mm to 228.40mm)				
2	UPVC 200mm dia ribbed screen	36		Mt	
	pipe conforming to IS 12818-1992				
	(outside dia 2.26mm to 228.40mm)				
3	Pebbles (8mm to10mm)	15		Cum	
B011					
4	Clay ball bag	600		No.	
1					
5	M.S Top cover 200mm dia	1		No.	
B013					
6	M.S. endcap (bottom cone) 200 mm	1		No.	
B0007	dia				
7	Mud bag	75		Nos.	
8	Jute (Five piri)	20		Kg	
9	1 ¹ / ₄ " x ¹ / ₄ " x 6" M.S flat	50		No.	
10	Welding rod 10 SWG	1		Poc.	
11	Waste	5		Kg	
12	Grease	10		Kg	
	Total				

All the materials should be got approved by the Engineer-in-charge before supply of site.

I hereby abide the rules and regulations stipulated in the CPWD form no. 6 & 8.

Contractor

Executive Engineer