

**PONDICHERRY UNIVERSITY COMMUNITY COLLEGE , LAWSPET**

**TENDER FORM for CCTV Surveillance System**

<b>Items</b>	<b>Description/Name of items</b>	<b>Req .Qty</b>	<b>Unit Price Rs.</b>	<b>Total Basic Price Rs.</b>	<b>VAT/ CST</b>	<b>Amount of VAT/CST %</b>	<b>Total including Rs.</b>
		<b>A</b>	<b>B</b>	<b>C=A X B</b>	<b>%</b>	<b>D</b>	<b>E=C+D</b>
1	<b>16 Channel Network Video Recorder</b> up to 16 Channel camera input ,H.265/H.264 codec decoding,Max 200Mbps Incoming Bandwidth,Up to 8MP Resolution for Preview and Playback, HDMI/VGA simultaneous video output,Support IPC UPnP, 16PoE ports,Support ANR technology to enhance the storage reliability when the network break down	1 No.					
2	2 Megapixel Color Outdoor Network IR Bullet Camera	12 Nos					
3	16 port PoE Switch (Brand - Cisco/Allied Telesis)	1 Nos.					
4	4 TB Hard Disk – NVR support SATA (Brand - Seagate /Western)-One Month Backup	2 Nos.					
5	Supply of 9U Rack (Brand –Valrack/HCL) Rack with tempered glass front door with lock and key , power strip with fuse and switch, Cable Manager ,Fan with tray and fixing charge	1No.					
6	Supply of CAT- 6 STP Cable (Best Net or Molex)	2 Boxes.					
7	Supply of CAT- 6 UTP Cable ( Molex)	3 Boxes					
8	CAT-6 Cable laying charge	1525 Mtrs					
9	Supply and fixing of 3”GI pipe &15 feet height 2”feet concrete, welding , power coated painting & other Accessories	As Req					
10	High Definition Video Balun ,DC connectors, Power Supply for (16 ) port ,PVC box 4X4 ,if any Accessories	As Req					
11	Excavation of trenching 1.5 m depth, top with 45 cm and bottom width 30 cm-BT surface and refilling of trenching Earth digging work, PVC Insulated Pipe Laying Work with Using Cement Brick Bed & Sand ,Civil work and Refiling Charges & Installation Charge,etc.	500 Mtrs					
<b>Total Amount Rs</b>							

\* Cable laying charges, PVC items, accessories, etc are at actual.

\* Item No.1 to 5 and 6,7 Onsite Comprehensive Warranty for One year.