

PONDICHERRY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of the work: Painting the Dining hall and Kitchen for the mess at Madam Curie hostel building.

S. No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1 11.3 6A	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS : 15622 (thickness to be specified by the manufacture of approved make (Jhonson / Asian / Somany / Nitco) in all colours, shades of size 200 x 300 mm as approved in skirting, risers of steps and dados over 12mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3 kg per sqm. Including pointing in white cement mixed with pigment of matching shade complete. - size 200x300mm	40		sqm	
2 14.4 3	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	254		sqm	
3 13.4 3.1	Applying one coat of cement primer of approved brand and manufacture on wall surface - Cement primer	236		sqm	
4 13.6 0.1C	Wall painting with plastic emulsion paint - Commercial of approved brand and manufacture to give an even shade - two or more coats on new work	236		sqm	
5 14.5 3.1	Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade - One or more coats on old work.	189		sqm	
6 14.4 2.2	White washing with lime to give an even shade - Old work (one or more coats).	160		sqm	
7 13.5 0.3	Applying priming coat: with ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanized iron/steel works.	19		sqm	
8 13.6 1.1	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade - Two or more coats on new work.	19		sqm	

9 14.5 4.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade - One or more coats on old work.	80		sqm	
	Total				

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within 20 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) The rate specified should be inclusive of GST.

EXECUTIVE ENGINEER