

PONDICHERRY UNIVERSITY
ENGINEERING WING

SCHEDULE OF WORK

Name of work: Providing ramp at Auditorium of convention cum cultural centre (Guest House-I)

S. No.	Description	Qty.	Rate Rs.P.	Unit	Amount Rs.P.
1. 4.1.10	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering.- All work upto plinth level -1:5:10 (1 cement:5coarse sand : 10 graded stone aggregate 40mm nominal size)	2.00		Cum	
2. 4.1.3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering.- All work upto plinth level -1:2:4 (1 cement:2coarse sand : 4 graded stone aggregate 20mm nominal size)	1.00		Cum	
3. 6.1.2	Brick work with FPS bricks of class designation 35 in foundation and plinth in cement mortar 1:6 (1 cement : 6 coarse sand)	1.00		Cum	
4. 13.3.2	20mm cement plaster of mix cement mortar 1:6 (1 cement : 6 fine sand)	2.00		Sqm	
5. 13.60.1C	Wall painting with plastic emulsion paint Commercial of approved brand and manufacture to give an even shade - two or more coats on new work	5.00		Sqm	
6. 10.28	Providing and fixing AISI 316 grade stainless steel hand rail of 50mm (outer dia 2mm wall thickness) stainless steel pipe supported on 40x10mm stainless steel flat at 600mm centre to centre to a total height of 900mm from the finished floor level and fixing 4nos .of 25mm (outer dia and 2mm wall thickness) stainless steel pipe as guard rails through the S.S.flat , with a base plate of size 100x100x8mm, including fixing in the base plate in concrete / wall surfaces by 4 nos of M-8 anchor fasteners and polishing the entire stainless steel work to no.4 surface finish as per the direction of engineer - in - charge	10.00		Rmt	
7. 11.51	Providing and laying 22mm thick factory made pre polished cement concrete flooring tiles of required	7.00		Sqm	

	colour and design over 20 mm thick cement mortar 1:4 (1 cement : 4 sand) and jointed with cement slurry mixed with an admixture of pigment to match the shade of the tile - (Endura \ Ultra \ Dazzle \ Technic)				
	Total				

Terms & Conditions:

- i) The rates specified are firm and not subject to any variation.
- ii) The work should be completed within a period of 20 days.
- iii) Payment will be made only after completion of the entire work.
- iv) The material should be got approved before commencement of work.
- v) The rate specified should be inclusive of GST.

Contractor

Executive Engineer