PONDICHERRY UNIVERSITY ENGINEERING WING

SCHEDULE OF WORK

<u>Name of the work:</u> Replacing the damaged floor tiles at first floor of examination building.

| S. No. | Description | Qty. | Rate Rs.P. | Unit | Amount Rs.P. |
|--------------------|---|------|---------------|------|-----------------|
| 1. 15.23.1 | Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50m lead - For thickness of tiles above 10mm and upto 25mm. | 200 | | Sqm | |
| 2. 11.41.2 C | Providing and laying fully vitrified floor tiles of size 60x60cm (thicknes to be specified by the manufacturer) with water absorption's less than 0.08% and conforming to IS: 15622 of approved make (Nitco / Rak / Johnson / Asian) in all colors and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 600x600mm.(Commercial quality) | 200 | | Sqm | |
| | Total | | | | |

I hereby abide the rules and regulations stipulated in the CPWD form no. 6 & 8.

Contractor

EXECUTIVE ENGINEER